

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan

(County)	Located in:	Corner Code #
1. Public Land Survey	T 2 N R 16 W	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1994 DEC 16 AM 9:56
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, George J. Mitchell in a field survey on November 4, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	15	14	13	12	11	10	9	8	7	6	5	4
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13

SEE BACK OF SHEET

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-11-94
 COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13

FOUND 1" PIPE FROM OLD WITNESSES AND ACCEPTED PIPE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

24" ASH EAST 19' TO CENTER
 CONCRETE MON AT CASCO TWP CORNER EAST 78.23'

MEASURED 2634.34 FEET WEST TO C-13 & 2654.65 FEET EAST TO E-13



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13

REPLACED PIPE WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.

A.C. remon tag & nail in South side of 19" Oak	AZ. 80°	27.09'
A.C. remon tag & nail in NW side of 12" Oak	AZ. 45°	12.93'
A.C. remon tag & nail in West side of 11" Oak	AZ. 350°	24.49'
Southwest corner of Corner fence post	AZ. 175°	2.49'
Casco Township Corner D-1	AZ. 90°	78.23'

Signed by George J. Mitchell Date November 4, 1994
 Surveyor's Michigan License No. 19618

LIB: 0005 PAGE 065

SEE BACK OF SHEET FOR SHEET 2

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Allegan

D-13 T2N, R16W
S1/4 POST, SECTION 32
GANGES TWP.

1831 S. SYRN - SET POST @ 40.00 CHAIN WEST
OF SE CORNER
7 BEECH N70W 41 Lks
7 IRONWOOD N51 1/2E 13 Lks

RATEKIN CARDS - (NO DATE) COPIED FROM OLD NOTES
STAKE & STONE
14" BEECH SOUTH - 32.0'
14" BEECH SE - 22.7'

1911 [faded] STAKE & STONE
SAME AS ABOVE
2634 WEST TO SW CORNER

MDOT 9/30/69 FENCE COR. POST - WEST - 1.14'
FENCE POST (3RD FROM COR.) - N10W - 18.42'
17" ASH N85E - 19.35'
5" POPLAR N50E - 9.94'
N1/4 POST, SEC.5, CASCO - EAST - 78.29

HOLLAND ENGINEERING - SAME AS MDOT 1969

MDOT 8/8/72 MDOT L.C.R.C L.2, P13
SAME AS MDOT 1969

MITCHELL 1994 FOUND 1" PIPE
24" ASH EAST 19' TO CENTER
CASCO CORNER EAST 78.23'