

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN COUNTY..... Located in: ...GANGES..... Township
Corner Code #

1. Public Land Survey T.2 N R.16W.....E-13.....
T..... R..... **SE COR. SEC 32**
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

97 JUN 22 PM 1:23
 REGISTERED
 ALLEGAN COUNTY MI
 REGISTER OF DEEDS STAMP & FILE NUMBER

1. **George J. Mitchell.....**, in a filed survey on **...October 21, 1996.....**
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner
points mentioned in lines 1 and 2 above were in conformance with regulations and rules
therefore as required in the current manual of survey instructions of the United States
Department of the Interior, Bureau of Land Management or by decree of a Court of Law
and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance
with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law;
established, re-established, monumented, re-monumented, recovered, found as expressed
below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11
3	1	2	3	4	5	6	7	8	9	10	11	12
4	2	3	4	5	6	7	8	9	10	11	12	13
5	3	4	5	6	7	8	9	10	11	12	13	14
6	4	5	6	7	8	9	10	11	12	13	14	15
7	5	6	7	8	9	10	11	12	13	14	15	16
8	6	7	8	9	10	11	12	13	14	15	16	17
9	7	8	9	10	11	12	13	14	15	16	17	18
10	8	9	10	11	12	13	14	15	16	17	18	19
11	9	10	11	12	13	14	15	16	17	18	19	20
12	10	11	12	13	14	15	16	17	18	19	20	21
13	11	12	13	14	15	16	17	18	19	20	21	22

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13

SEE SHEET 2 OF 2 FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-12-96
COUNTY REP. Dist. 2 - Van Orden



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13

FOUND 1" PIPE FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 12, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13

REPLACE 1" PIPE WITH ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP.

A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 14" MAPLE	AZ.	285°	20.35 FEET
A.C. REMON TAG & NAIL IN WEST SIDE OF 12" TRIPLE MAPLE	AZ.	355°	17.30 FEET
A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF POWER POLE	AZ.	40°	108.63 FEET
A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF POWER POLE	AZ.	140°	107.85 FEET
CENTERLINE OF NORTH-SOUTH ROAD	AZ.	90°	35.0'
CASCO TOWNSHIP CORNER	AZ.	90°	63.05 FEET

Signed by George J. Mitchell Date November 12, 1996
Surveyor's Michigan License No.19618.....

SHEET 1 OF 2

GOVERNMENT CORNER HISTORY
SOUTHWEST CORNER OF SECTION 33
TOWN 2 NORTH, RANGE 16 WEST

E-13

ORIG. GOVERNMENT SURVEY	WEST ON SOUTH SEC 33 40.00 SET QUARTER POST 80.00 CH SET POST SEC 32 & 33 12 BIRCH N77W 20 LKS 6 BIRCH N47E 34 LKS
MDOT 9/30/69	1" IRON ROD FD. WEST SIDE OF ROAD IN DITCH 18" CHERRY N55W 23.31' 5" POPLAR S10W 6.87' 9" POPLAR S45E 11.60' CASCO CORNER - EAST 63.00'
MDOT 8/8/72	L.G.R.C. L.2, P.14 SAME AS ABOVE
H.E.I.	SME AS ABOVE
RATAKIN WITNESS CARD	SAME AS ABOVE
MITCHELL 6/12/86	FD 1" IRON BAR 18" CHERRY NW 13.3' 6" POPLAR SSW 6.9' CASCO CORNER - EAST- 62.94'
MITCHELL 10/96	FOUND 1" PIPE OLD WITNESSES VERIFY LOCATION