

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in _____

ALLEGAN
(County)

Located in: Ganges Corner Code #

1. Public Land Survey	T	<u>2N</u>	R	<u>16W</u>	F-1
	T		R		<u>N 1/4 SEC 4</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO006 PAGE384

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Lemke, in a field survey on April 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: (see back of page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Old Allegan County survey records show F-1 to G-1 = 1313.9 + 1313.9. Set F-1 on the South line of Section 33, Town 3 North, Range 16 West 2627.8 feet West of G-1. This position fits unrecorded surveys in the Northwest 1/4 and the Northeast 1/4 of Section 4. Found old North & South fence 250 feet South of F-1 to be on said South 1/4 line. (Information provided by Holland Engineering)

Found PK nail
E-1 to F-1 Measured 2618.67 (Shown as 2618.63' Holland Eng. Sec. 4, T2N,R16W)
F-1 to G-1 Measured 2627.75 (Shown as 2627.80' Holland Eng. Sec. 4, T2N,R16W)

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PK nail & **RED CAP # 23520**
Set standard Allegan Co. Remon tag & nail in the South side of a 26" Maple 1.5' above grade N 15° E 71.19'
NW corner house foundation S 65° E 182.30'
NE corner house foundation S 20° W 129.00'
Set standard Allegan Co. Remon tag & nail in the West side of a 24" Elm 1.3' above grade S 5° W 43.85'
Drill hole in the top center of the East end of a 10" ID concrete culvert S 70° W 89.85'
Centerline E&W asphalt road pavement S 0° W 7.24'
F-13 T3N, R16W 270°31'31" 4.34'
G-1 90°31'31" 2627.75'



APPROVED REMONUMENTATION CORNER
P.A.345 OF 1990
ALLEGAN COUNTY
DATE APPROVED April 14, 1998

COUNTY REP. *[Signature]*

Signed by Robert E. Lemke
Surveyor's Michigan License No. 40160 for SDI Consultants

Date 12/29/98

F-1
GANGES TWP.

A. Description of original monument and accessories and/or subsequent restoration: F-1 continued:

GLO
Not set by GLO

MDOT Right-of-way Map
Late 1920's
F-1 not shown

County Witness Card Sec. 4, T2N, R16W
Unknown Date
N 1/4 Post "Stone"
Maple 6" N. 26.0'
Maple 12" SE 32.0'

Old Allegan County Survey records
F-1 to 10 = 1313.9 and 10 to G-1 = 1313.9

Holland Engineering Section Break
Section 4, T2N, R16W
Distance E-1 to F-1 2618.63
Distance F-1 to G-1 2627.80