

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: ...GANGES... Township
Corner Code #

1. Public Land Survey T 2 N. R. 16 W. F13
2. Property Controlling S..... T..... R.....
in Section S..... T..... R..... 5/4 Post, Sec 33
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No. Recorded Plat
5. Private Claims.....

97 JAN 22 PM 1:23
REGISTERED
ALLEGAN COUNTY
FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell, in a filed survey on October 21, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13

SEE SHEET 2 OF 2 FOR CORNER HISTORY



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13

FOUND PINCH PIPE FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 12, 1996
APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED 11-12-96
COUNTY REP. Bill E. VanCleave

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13

REPLACED PINCH PIPE WITH ALLEGAN COUNTY STANDARD 3/4" BY 3/8" IRON PIN WITH REMON CAP.

| | | | |
|--|-----|------|------------|
| A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 12" ELM | AZ. | 85° | 38.57 FEET |
| A.C. REMON TAG & NAIL IN EAST SIDE OF 8" TWIN ELM | AZ. | 00° | 11.45 FEET |
| A.C. REMON TAG & NAIL IN EAST SIDE OF 10" ELM | AZ. | 350° | 20.35 FEET |
| A.C. REMON TAG & NAIL IN WEST SIDE OF POWER POLE | AZ. | 135° | 74.60 FEET |
| CASCO TOWNSHIP CORNER | AZ. | 90° | 52.04 FEET |

Signed by George J. Mitchell Date November 12, 1996
Surveyor's Michigan License No. 19618

SHEET 1 OF 2

1152P 0005 PACF 386

GOVERNMENT CORNER HISTORY
SOUTH QUARTER POST OF SECTION 33
TOWN 2 NORTH, RANGE 16 WEST

F-13

| | |
|-------------------------|--|
| ORIG. GOVERNMENT SURVEY | WEST ON SOUTH SEC 33 40.00 SET QUARTER POST 14 PINE N74E 16 12 PINE N69.5 28 |
| MITCHELL 10/26/88 | FD PINCH PIPE 6" ASH NORTH 11.60' 20 ASH NNE 19.30 6 ASH ENE 38.50 CASCO COR EAST 52.0 EAST EDGE/POND-WEST 3 FT |
| MITCHELL 11/30/88 | L.C.R.C. L.4, P.52 SAME AS ABOVE |
| H.E.I. | SAME AS ABOVE |
| MITCHELL 10/96 | FOUND PINCH PIPE CASCO CORNER EAST 52.0' CORNER IS ON FENCE LINE TO NORTH |

