

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

.....ALLEGAN ..... Located in: **.GANGES..... Township**  
Corner Code #

1. Public Land Survey T..2..N R..16 W .....G-13.....  
T..... R..... SW COR, SEC 34
2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....
4. Lot No. ...., Recorded Plat .....
5. Private Claims.....

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0006 PAGE388

I, **George J. Mitchell**....., in a filed survey on **10/26 thru 11/11/98**..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1	6	5	4	3	2							
2												
3												
4	7	6	5	4	3	2	1					
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 CALVIN BRITAIN SET POST AT 80 CHAINS  
BEECH 10 N54W 17 LKS SUGAR 12 N77E 50 LKS

1980 GEORGE MITCHELL P.S. FD 1" IRON 8" W. CHERRY WEST 28.0'  
P. POLE WSW 106.3' CL ROAD EAST 21.5' CASCO COR. EAST 41.6'

1998 GEORGE MITCHELL P.S. FD 1" IRON P. POLE ESE 106.4'  
CENTER ROAD EAST 21.5' CASCO CORNER EAST 41.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13) FOUND 1" IRON BAR FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13) SOUTHWEST CORNER OF SECTION 34, TOWN 1 NORTH, RANGE 16 WEST

REMOVED 1" IRON BAR AND SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. REMON TAG & NAIL IN N. SIDE OF 14 TWIN BOX ELDER	AZ.	274°	28.71 FEET
A.C. REMON TAG & NAIL IN NW SIDE OF 36" MAPLE	AZ.	180°	203.16 FEET
A.C. REMON TAG & NAIL IN SW SIDE OF POWER POLE	AZ	125°	106.31 FEET
CASCO TOWNSHIP CORNER	AZ	090°	41.50 FEET
CENTERLINE OF 66TH STREET	AZ	090°	21.0 FEET
MEASURED G-13 TO H-13			2630.89 FEET

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED Nov. 10, 1998  
COUNTY REP. [Signature]

Signed by George J. Mitchell  
Surveyor's Michigan License No. ....19618.....

Date Nov. 12, 1998

