

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

.....ALLEGAN..... Located in: GANGES..... Township
Corner Code #

FILED

1/28/1999 2:44:39 PM

1. Public Land Survey T..2..N R..16 WH-13.....
T..... R..... S1/4 POST, SEC. 34
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

JOYCE A. MATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0006 PAGE391

I, George J. Mitchell, in a filed survey on 10/26 thru 11/11/98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	18	17		16		15		14		13			
7													
8	18	20		21		22		23		24			
9													
10	30	29		28		27		26		25			
11													
12	31	32		33		34		35		36			
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831 CALVIN BRITAIN SET POST
HEMLOCK 8 N72E 5 LKS HEMLOCK 16 43W 13 LKS

1994 GEORGE MITCHELL P.S. FD IRON NO WITNESS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13) FOUND 1" IRON BAR FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13) SOUTH QUARTER POST OF SECTION 34, TOWN 2 NORTH, RANGE 16 WEST

REMOVED 1" IRON BAR AND SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. REMON TAG & NAIL IN S. SIDE OF 30" OAK	AZ.	090°	47.00 FEET
A.C. REMON TAG & NAIL IN W. SIDE OF 18" ASH	AZ.	000°	10.00 FEET
A.C. REMON TAG & NAIL IN NW SIDE OF POWER POLE	AZ.	150°	47.50 FEET
A.C. REMON TAG & NAIL IN NE. SIDE OF 12" HEMLOCK	AZ.	320°	34.85 FEET
CASCO TOWNSHIP CORNER	AZ.	090°	57.00 FEET
MEASURED H-13 TO I-13			2629.47 FEET
MEASURED H-13 TO G-13			2630.89 FEET

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED NOV. 10, 1998
COUNTY REP. Rich T. Van Oort

Signed by George J. Mitchell
Surveyor's Michigan License No. 19618

Date Nov 17, 1998

