

RF

FILED

MAR 17 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB -1 AM 8:38

Joyce A. White

REGISTER OF DEEDS
ALLEGAN COUNTY

ENER0007 PAGE 2 54

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>16W</u>	<u>K-6</u>
	T ___ R ___	<u>Ganges</u> Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Kirk L Van Order in a field survey on Dec 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-6
(1) GLO post established by U.S. Deputy Surveyor C. Britain in 1831 North between Sections 13 & 14 (N6°30'E) 40.00 set quarter sec. post
Maple 6 S20W 5 links
Lynn 12 N45E 14 links

(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6
Fd. standard Allegan Co. Remon. monument in mon. box and the following accessories:
S58W 44.50', Chiseled "x" on rivet on South end 6' CSP
N51W 46.81', Chiseled "x" on North end 6' CSP
S80E 42.98', Nail & DNR tag in 6" cedar
And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved Dec. 28, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6
Standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520)
Chiseled "x" on rivet on top S. end 6' CMP S.58°W. 44.50'
Chiseled "X" on top N. end 6' CMP N.51°W. 46.81'
Nail & DNR tag in N. side 6" cedar S.80°E. 42.98'
On C/L inter-x of 62nd St. & 119th Ave.

Signed by *Kirk L. Van Order*
Surveyor's Michigan License No. 23520

Date _____



APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC 28 1999
COUNTY REP. *Kirk L. Van Order*

DIVISION
RECORDS SECTION

MAR 07 2000

SECTION

Section A (continued from Page 1)

K-6

Ganges Twp., T.2N., R.16W.

- (2) Wightman-Moored info undated records
1" iron
St. sign N65E 21.90'
NW corner shed S85E 47.49'
SW corner shed S50E 55.05'
Nail in 6" cedar S86E 32.17'
Centerline road 4' East, in centerline 119th Ave. to West
K-5 North 2622.46'
K-7 South 2622.46'
- (3) D.A. Ratekin Assoc., Inc. no date given
1/4 post 1" iron
St. sign N65°E 21.90'
NW cor. shed S50°E 55.05'
Nail 6" cedar S86°E 32.17'
C/L rd 4.5' E
In C/L to West
- (4) Mitchell Survey, Inc. info
Ganges Twp.
K-6
Recovered 1" bar 1994
T.C.B. SW 63.60'
6" cedar E,SE 43.0'
Nail in guardrail post NW 38.90'
- (5) Thomas W. Benson, DNR Surveyor, info dated Dec. 14, 1995
Found 5/8" rerod and none of above accessories. Distance to adjacent corners checked with recovered data. Replaced 5/8" rerod with standard Allegan Co. Remon. 3/4" x 24" iron with red cap 23520.
East 34.09', 1/2" rerod with cap "T W Benson 41091"
S58W 44.50', chiseled "x" on rivet on South end 6' CSP
N51W 46.81', chiseled "x" on North end 6' CSP
S80E 42.98', Nail & DNR tag in 6" cedar
East 1', Centerline 62nd Street
North 3', Centerline 119th Avenue

RECORDS SECTION / MAR 07 2000