

RF

FILED

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE 00 FEB -1 AM 8:39
Filing Requirement of Act 74, Mich. P.A. 1970

USNO 007 PAGE 260

SECTION

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>16W</u>	<u>K-9</u>
	T ___ R ___	<u>Ganges Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Joyce A. White

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Orden in a field survey on Sept 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-9
Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: Tamarack 7 S4E 53 links & Tamarack 10 N36E 85 links. Records obtained from Wightman-Moored state "3/4" iron over stone - accessories: Fence post WNW 24.95', 3" Ash WSW 29.25', 17" Maple SSW 104.4', 8" Cherry ESE 49.8". Next reference states "1" pipe over 3/4" iron - accessories: Nail in Guard post N15W 22.37', Nail in Guard post S10W 28.80', Tel. outlet NE corner S50W 53.43', Cl 62nd St. East 9', Cl 116th Ave South 4". No other records found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-9
Fd. 1" iron pipe and two of the above accessories. Distances to adjacent corners checked with recovered data. Replaced 1" iron pipe with standard Allegan Co. Remon. 3/4" x 24" iron w/red cap #23520. And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved April 13, 1999.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED APRIL 13, 1999
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9
Fd. standard Allegan Co. Remon. monument (3/4" x 24" steel rod in mon. box)
Nail & Remon. tag in NE side power pole AZ 138°34' 108.64'
Nail & Remon. tag in NW side power pole AZ 26°12' 168.67'
Nail & Remon. tag in SE cor. wood ret. wall AZ 309°11' 21.34'
Nail & Remon. tag in top guard rail post AZ 236°23' 37.77'
C/L asphalt road AZ 90° 8'

Signed by Kirk L. Van Orden
Surveyor's Michigan License No. 23520
PROFESSIONAL SURVEYOR
No. 23520
LICENSED PROFESSIONAL SURVEYOR

Date 12-30-1999