

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
 For corners in
 Allegan

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> N <u>16</u> W T _____ R _____ T _____ R _____ T _____ R _____	K-12 _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

1993 DEC 30 PM 2:45
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 J. A. [Signature]
FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	12	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, George J. Mitchell, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	<u>K-12</u>		
G.L.O. Notes	MacDougalls note book	Mitchell 1978	
North between sec 35 & 36 40 ch set post	3" iron & Stake	fd. 3/4" Iron bar	
Hemlock 20" S76W 301ks	26" Maple SW 26.8'	Power Pole NE 68.45'	
Hemlock 18" S34E 271ks	St, Sign SE 38.8'	18" Maple NW 100.16'	
	SE cor School 92.8'	T.C.B. SE 70.60'	
		Power Pole NNW 95.72'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12
 Found 3/4" iron bar 5" below asphalt road surface and accepted it as a careful and faithful perpetuation of the position of original corner.

20" Maple	N68W	100.27'
Power Pole	N17W	95.81'
Power Pole	N40E	68.51'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12
 Replaced 3/4" iron bar with A.C. remonumentation 3/4" iron & cap.

A.C. remon tag & nail in SW side of 20" Maple	AZ. 292°	100.21'
A.C. remon tag & nail in East side of Power Pole	AZ. 343°	95.73'
A.C. remon tag & nail in NW side of Power Pole	AZ. 40°	68.38'
A.C. remon tag & nail in West side of Power Pole	AZ. 170°	258.39'

Signed by George J. Mitchell Date 12-29-93
 Surveyor's Michigan License No. 19618

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983