

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Allegan
(County)

Located In: Ganges Township Corner Code # L-13

T 2 N R 16 W

T _____ R _____

T _____ R _____

T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

George J. Mitchell
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

1994 DEC 16 AM 9:54

FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	3	4	5	6	7	8	9	10	11	12	13	14
3	4	5	6	7	8	9	10	11	12	13	14	15
4	5	6	7	8	9	10	11	12	13	14	15	16
5	6	7	8	9	10	11	12	13	14	15	16	17
6	7	8	9	10	11	12	13	14	15	16	17	18
7	8	9	10	11	12	13	14	15	16	17	18	19
8	9	10	11	12	13	14	15	16	17	18	19	20
9	10	11	12	13	14	15	16	17	18	19	20	21
10	11	12	13	14	15	16	17	18	19	20	21	22
11	12	13	14	15	16	17	18	19	20	21	22	23
12	13	14	15	16	17	18	19	20	21	22	23	24
13	14	15	16	17	18	19	20	21	22	23	24	25

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 L. LYON SET POST 1831
SET POST AT 40 CHAINS WEST
HEMLOCK 12 N85W 19 lks
BLACK ASH 9 N60E 23 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

L-13 NO CORNER FOUND. SET CORNER ON SPLIT DISTANCE BETWEEN K-13 AND M-13 ON AN EXISTING EAST-WEST FENCE & OCCUPATION LINE AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

MEASURED 2637.86 FEET WEST TO K-13 AND 2637.86 FEET EAST TO M-13

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-29-94
COUNTY REP. Bob L. Van Orden



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

L-13 SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. remon tag & nail in SW side of 18" Cherry	AZ. 90°	23.60'
A.C. remon tag & nail in East side of 8" Cherry	AZ. 03°	47.46'
A.C. remon tag & nail in South side of 20" Cherry	AZ. 270°	77.34'
Gas Line Marker Post	AZ. 270°	12.70'
Casco Township Corner L-1	AZ. 90°	21.88'

Signed by George J. Mitchell Date December 12, 1994
Surveyor's Michigan License No. 19618

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 0005 PAGE 020