

FILED

MAR 17 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

00 FEB -1 11 8 40

SECTION

For corners in

Allegan (County)	Located in:	Corner Code #
1. Public Land Survey	T2N R16W	M-10
	T___ R___	Ganges Twp.
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Joyce A. ...
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

RECORDED / PART 2 OF 6

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L Van Order in a field survey on Dec 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-10
(1) GLO post established by U.S. Deputy Surveyor L. Lyon in 1831
North East side Sec. 25
40.00 set quarter section post
Beech 7 S60W 8
Do 9 N17W 15
- (2) Hugh McDougall note book dated early 1900's
Shows each 1/2 mile to North and South to be 2629'. A stone midway
between M-11 and M-10 cherry 14 NW 326. (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-10
Fd. standard A.C. Remon. monument and the accessories as listed in No. 6 of Part A. And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved April 13, 1999.

APPROVED REMONUMENTATION CORNER
P.A. 365 OF 1990
ALLEGAN COUNTY
DATE APPROVED APRIL 13, 1999
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10
Standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520)
- | | | |
|--|----------|-----------------|
| Nail & DNR tag in NW side 11" scotch pine | S. 65°W. | 62.09' |
| Nail & DNR tag in S side 17" white pine | N. 70°W. | 83.58' |
| Nail & DNR tag in NE side sawed off p. pole | N. 15°W. | 158.97' |
| Nail & DNR tag in NW side 12" white birch | N. 35°E. | 70.19' |
| SE corner mobile home fndn. | N. 65°W. | 88.35' |
| Fd. 3/8"x1/2' steel rod w/pointed & hooked top | S. | 9.08' (removed) |
| A-10, T.2N., R.15W. | North | 20.56' |

Signed by *[Signature]*
Surveyor's Michigan License No. 23520



Date 12-30-1999

MAR 07 2000

SECTION

LIBR0007 PAGE 89

Section A (continued from Page 1)

M-10

Ganges Twp., T.2N., R.16W.

- (3) Wightman-Moored info dated May 1969 shows found 2" iron raised with 3/4" iron
Tel. pole N.NE 77.85' M-9 North 2662.34'
Tel. pole SE 61.75'
Corner fence post E.NE 27.82'
- (4) Donald A. Ratekin survey Job #78-5225 list same info as in No. 3
- (5) Holland Eng., Inc. info dated Dec. 31, 1987
Fd. 3/4" iron
NE - SW corner house #1513 166.14'
WNW - 12" pine 53.77'
NW - 4" maple 54.88'
SW - N. side 8" pine 62.75'
Iron ? S. 9.4'
- (6) Thomas W. Benson, DNR Surveyor info dated Jan. 9, 1996
Fd. 5/8" rerod and none of the above accessories. Replaced 5/8" rerod with standard Allegan Co. Remon. 3/4" x 24" iron with red cap 23520.
N62W 88.40', SE cor. house trailer #1468 (M - 88.35')
N70W 83.61', Nail & DNR tag in 16" pine
S65W 62.06', Nail & DNR tag in 8" pine
35E 70.14', Nail & DNR tag in 8" birch
South 9.33', Pointed iron
North 2662.30', M-9, T.2N., R.16W.
South 2627.79', M-11, T.2N., R.16W.