

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Allegan  
 (County)

Located In: Corner Code #/

- |                                    |               |            |            |
|------------------------------------|---------------|------------|------------|
| 1. Public Land Survey              |               | T 2N R 16W | M4         |
|                                    |               | T 2N R 16W | MC N of M5 |
|                                    |               | T R        |            |
|                                    |               | T R        |            |
| 2. Property Controlling in Section | S 12          | T 2N R 16W | 9          |
|                                    | S             | T R        |            |
| 3. Miscellaneous Property in Sec.  | S             | T R        |            |
|                                    | S             | T R        |            |
| 4. Lot No.                         | Recorded Plat |            |            |
| 5. Private Claims                  |               |            |            |

Register of Deeds Stamp & File Number

1. Gary C. Bilow in a field survey on 9 April 14, 1993  
MC April 09, 1993  
M4 April 14, 1993 19

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 M4: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: B. Ash 7 S48W 7 and Maple 20 N10W 20. Corner recorded under Act 74 PA 1970 in Liber 2 Page 295 by D. Ratekin (PS 8781) as "Set 1" solid bar 6' long equal distance and on a straight line from NE and SE corner Section 12 - accessories: Centerline North-South ditch, 14" W. Cherry S2W 20.4', and Fence N 61". D. Ratekin also shows this corner on a Certified Survey recorded in Liber 841 Page 517 listing same accessories.  
 MC N of M5: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: Tamarack 7 S69E 42 and Willow 6 S61W 62. No other records found.  
 9: Post not established by U.S. Government survey. Corner recorded under Act 132 PA 1970 in Liber 841 Page 517 by D. Ratekin as "Iron - accessories: Centerline North-South ditch, 12" W. Cherry N50W 9.6', 6" Box Elder N30E 13.1', and 3" Poplar N80W 3.8".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 M4: Found 1-1/2" iron pipe 0.2' below water surface and two (2) of Ratekin's witnesses. A comparison of measured distances to the card index of Section 12 obtained from Wightman-Hoored checked (2643.81 measured vs 2643.54, 2643.27 measured vs 2643.54, and 2621.70 measured vs 2622.46). Accepted 1-1/2" iron pipe as the best evidence of the original GLO post.  
 MC N of M5: Reestablished corner at single proportionate distance (GLO 712.80 to 713.83 prorated) between corners M5 and M4 (both recorded this date).  
 9: Found 1" iron bar with cap (PS 8781) in centerline of North-South ditch projecting 0.2' above water surface and none of Ratekin's witnesses. Comparison of measured distances to adjacent corners vs record distances were reasonable and consistent. Accepted capped iron bar for this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M4: Left 1-1/2" iron pipe in place Centerline North-South ditch East 1', Steel post S10W 20.38', Nail & Tag in 18" Cherry S1E 85.03', 1" iron pipe N31W 24.35', Nail & Tag in 5" Cherry S23W 69.34', Capped iron (PS 23520)	MC N of M5: Set 1/2" x 24" rebar with plastic cap stamped "G.C. Bilow LLS 26453" South 1', 1-1/2" iron pipe projecting 2.5' above ground West 4', East edge North-South ditch South 36', Intersection of ditches	9: Left 1" capped iron bar in place South 26', Ditch going west SSW 0.8', 1" iron pipe S88E 16.28', Nail & Tag in twin 5" Ash S24E 29.52', Nail & Tag in 5" Ash Centerline North-South ditch
---	---	---

Signed by Gary C. Bilow Date 5/6/93  
 Surveyor's Michigan License No. 26453



*Handwritten initials: P.W. 200*