

COPY

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alleghan County Located in: Hopkins Corner Code #  
 (County) Twp., Martin Twp., Watson Twp., & Wayland Twp.

1. Public Land Survey T2N R11W \* A-1 MARTIN  
 T R NW Cor. Sec. 6  
 T3N R11W \* A-13 WAYLAND  
 T R SW Cor. Sec. 31

2. Property Controlling S T3N R12W M-13 HOPKINS  
 in Section S T R SE Cor. Sec. 36

3. Miscellaneous S T2N R12W M-1 WATSON  
 Property in Sec. S T R NE Cor. Sec. 1

97 JAN 22 PM 1:26  
 REGISTERED  
 ALLEGAN COUNTY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A-1											M-1			
T2N, R11W											T2N, R12W			
1	A	B	C	D	E	F	G	H	I	J	K	L	M	
2	6	5	4	3	2	1								
3														
4	7	6	5	4	3	2	1							
5														
6	10	9	8	7	6	5	4	3	2	1				
7														
8	13	12	11	10	9	8	7	6	5	4	3	2	1	
9														
10	30	29	28	27	26	25	24	23	22	21	20	19	18	
11														
12	31	30	29	28	27	26	25	24	23	22	21	20	19	
13														
A-13											M-13			
T3N, R11W											T3N, R12W			

I, Robert Jonker, in a field survey on July 9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 85.85 ch., set post, T2 & 3N, R11 & 12W  
 Birch 18 N 81 W 4  
 Do 7 S 77 E 15

Old county surveyor notes, no date, call for stone & brick  
 Blass wit., no date, 3/4" iron pipe  
 39" Elm N 37° E 29.77'  
 18" W.Ch. S 10° E 23.86'  
 M.B.T. pole S 68° W 49.91'

APPROVED REMONUMENTATION CORNER  
 P.A. 343 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 7-9-96  
 COUNTY REP. Robert J. Jonker

(OVER)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.  
 Found 3/4" boat spike in mon. box on bridge on West side of US-131 on C/L  
 E-W pavement as per wit. listed in "A" above per 1974 & 1977 wit.  
 Replaced with 3/4" x 24" standard Alleghan County capped monument.

B-13, T3N, R11W, East 3040.68'  
 B-1, T2N, R11W, East 3182.20'

Accepted as a careful & faithful perpetuation of the position of the original corner.  
 Approved by the Alleghan County Remonumentation Peer Group on July 9, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.


Alleghan County Monument

Nail & tag in top of wooden guardrail post	S 56° W	31.52'
Nail & tag in top of wooden guardrail post	N 49° W	30.22'
SW corner of SW conc. abutment	S 43° E	26.61'
NW corner of NW conc. abutment	N 55° E	29.47'
W. edge of bridge	East	33.71'

Nail & tags are Alleghan Co. Remon. tags.

Signed by Robert J. Jonker  
 Robert J. Jonker, P.S.  
 Surveyor's Michigan License No. 21572

Date November 26, 1996



COPY

A-1 MARTIN TWP.

Part "A" cont'd

Ratekin, 1974 & 1977

3/4" boat spike in box

In C/L road 33.8' West of W. end bridge

SW corner of SW abutment S 50° E 26.6'

NW corner of NW abutment N 50° E 29.51'