

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For comers in
Allegan County
(County)

Located In:
Wayland Twp. Corner Code #

- | | | |
|------------------------------------|--------------------------|--------------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>11W</u> | <u>B-13</u> |
| | T _____ R _____ | <u>S 1/2 Cor. Sec 31</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

97 JAN 22 11 18 28
 REGISTER OF DEEDS
 ALLEGAN COUNTY
 FILED
 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert Jonker, in a field survey on July 09, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a Decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

40.00 Ch. Set gr. sec. post	LCRC 3-409, 1985, Jonker, 1" Steel Pin
Birch 7 N 76 1/2 E 26	PK - N. side P. pole WSW 147.45'
Sugar 8 N 75 W 29	C/L R.R. fe. post North 32.05'
Co. Surveyor Hicks, 1888, set stone	1" St. pipe East 141.8'

(OVER)

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 7-9-96
 COUNTY REP. Robert J. Jonker

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" solid pipe 2.5' South of C/L of E-W paved road
 Replaced with 1" x 36" standard Allegan County capped monument

A-13, T3N, R11W, West 3040.68'
 C-13, T3N, R11W, East 2649.74'

Accepted as a careful and faithful perpetuation of the position of the original corner.
 Approved by the Allegan County Remonumentation Peer Group on July 9, 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan County capped monument
 PK Nail on North side P. pole S 82° W 147.55'
 C/L R.R. rail fence post N 4° E 32.10'
 Capped 3/4" solid pin in mon box East 141.78'
 Nail & Tag, top of wood fe. post N 42° E 45.04'

Nail & tag is an Allegan Co. Remon. tag.



Signed by Robert J. Jonker Date November 29, 1996
 Robert J. Jonker, P.S. Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

B-13 WAYLAND TWP.

Part "A." cont'd

County Surveyor, 1977

Found 3/4" pipe - placed 1" iron over S. edge rail N. 31'87'

Nail N. side P. pole S 70° W 147.45'

C/L W. end C.M.P. (12") S 80° E 53.8'

C/L E. end C.M.P. (12") S 75° E 76.07'

Fence line to South is East 143'±

SE corner East 2650.12'

Bless Surveys

1/2" iron down 1.3'

14" Cherry S 55° E 31.88'

M.B.T. pole S 65° W 54.88'

C.P. pole N 75° W 150.56'

R.R. iron set in conc.

N 3° W 32.06'

Gregory G. Adams
REGISTERED PLT.
ALLEGANY COUNTY, PA.

97 JUN 22 PM 1:28

FILED