

SURVEY & REMONUMENTATION

FL
8

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Allegan</u> (County)	Located in: Wayland Twp.	Corner Code # <u>1 C-3</u>
1. Public Land Survey	T <u>3N</u> R <u>11W</u>	<u>1 C-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

98 JAN 21 PM 1:37

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on 12-27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey 1831	LCRC #1-24, 1972 Ratekin	3) PK Nail	1997
80.0 set post, cor. sec. 5, 6, 7 & 8	Part "A" - 1) stone	12" Maple N40°W 35.47'	o.k.
B. Ash 10 N 15	2) stake	12" Maple N30°E 57.19'	o.k.
Pine 6 S 14	Poplar 30 SW 67.2' out '97	P.Pole East 25.64'	o.k.
	Poplar 33 SW 38.5' out '97	18" Maple W 46.25'	o.k.
	Fe. post W 31.2' out '97	Near cor. CB SW 23.39'	o.k.
		Near cor. CB SE 28.10'	o.k.
		C/L pavt E 3'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" (head) x 20" x 1/2" (bottom) tapered rod.
Top bent to South by 0.1' - held vertical shaft


APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-30-97
COUNTY REP. K.V.O.

Accepted as the best available evidence of the position of the original corner.

Peer group approved Dec. 30, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with Std. Allegan Co. Mon.	
Fd. PK nail on N side P.Pole	N84°W 39.66'
Fd. spk. NE side 18" Maple	N33°W 35.68'
Fd. sq. spk. SE side 16" Maple	N35°E 57.40'
Fd. PK nail N side P.Pole	S84°E 26.22'
C/L W-S part. E. 3'±	



Signed by Robert J. Jonker
Surveyor's Michigan License No. Robert Jonker P.S. 21572

Date Dec. 30, 1997

C-3, T3N, R11W
 LCRC #1-24 con't.

Part "B" - Set 1" iron from witnesses

Part "C" - 1" iron

C/L part E. 3'

1997

Spk. in P.Pole W. 39.68' checked o.k.

Spk. in 12" Maple N30°E 57.45' checked o.k.

12" Maple N40°W 35.47' checked o.k.

Near cor. catch basin S70°W 23.39' checked o.k.

Near cor. catch basin S70°E 28.10' checked o.k.

1982 - M.V.K. - suvey recorded in L. 1053, P. 72

1" iron

Spk. P.Pole W 39.68' o.k. 1997

Spk. 12" Maple N30°E 57.45' o.k. 1997