

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan County
(County)

Located in: Wayland Twp. Corner Code #

- | | | |
|------------------------------------|---|------------------------|
| 1. Public Land Survey | T <u>3</u> N R <u>11</u> W | <u>C-13</u> |
| | T <u> </u> R <u> </u> | <u>SE Cor. Sec. 31</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

ALLEGAN COUNTY REGISTER OF DEEDS

97 JUN 22 PM 1:29

FILED

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on July 09, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

80.00 Ch. set post corner Sections 31 & 32
Birch 6 N 84 E 46
Do 18 N 67 W 30

LCRC - SEE OVER

County Surveyor, old notes NW corner Bldg. 69.1
Fe. post SW 65.5' 1980, per Ratekin, placed PK nail site. same per LCRC (see over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK by witnesses listed in "A" above.


B-13, T3N, R11W, West 2649.74'
D-13, T3N, R11W, East 2649.74'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 7-9-96
COUNTY REP. [Signature]

Accepted as a careful & faithful perpetuation of the position of the original corner.
Approved by the Allegan County Remonumentation Peer Group on July 9, 1996.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

Replaced P.K. Nail with Standard Allegan Co. Mon.
Found PK nail in top wooden guardrail post N 28° W 42.73'
NE corner of conc. sign base S 53° E 59.81'
Nail & Tag - S. side P. pole S 65° W 55.91'
Found PK nail in SE side P. pole N 64° E 69.92'
NE corner Sec. 6, Martin Twp. East 181.45'



Signed by Robert J. Jonker
Robert J. Jonker, P.S. 21572
Surveyor's Michigan License No.

Date November 26, 1996

USER:0005 PAGE 513

C-13 WAYLAND TWP.

MAY 2 1937

Part "A." cont'd

LCRC 3-409, 1984, Jonker Land Surveys
PK Nail

Martin corner East 181.52'

SE corner rim of C.B.

NE corner conc. base to Union 76 sign

SE corner conc. base to cable box

SW corner S. end conc. ret. wall

PK nail NE'ly 0.5'

N 65° W	49.09'
S 60° E	59.88'
S 65° W	59.23'
N 45° E	31.42'