

REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In: Wayland Township	Corner Code #
1. Public Land Survey	T3N R11W	1 D-1
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

98 JAN 21 PM 1:37

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on Jan. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Not set in GLO survey

LCRC #2-97 W & W, 1973  
Part A - no info. listed  
Part B - no info. listed  
Part C - "T" iron

Part C con't - took wit.  
6" W. Cherry N80°W 35.22'  
26" Ash N85°W 10.2'  
Fe. cor. N70°W 52.39'  
+ on stone W. 50.00'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 4-8-97  
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found "T" iron by the following witnesses listed in A above.  
6" W. Cherry N80°W 35.22'  
26" Ash N85°W 10.2'  
Fe. corner N70°W 52.39'

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Peer group approved April 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced "T" iron with 3/4" x 36" std. capped Allegan Co. Mon. on Twp. line  
Allegan Co. Remon Tag on N. side 34" Ash N 75° W 9.93'  
Allegan Co. Remon Tag on N. side 16" W.Ch. S 85° E 40.43'  
Allegan Co. Remon Tag on N. side 24" Maple S 35° E 51.28'  
Allegan Co. Remon Tag on E. side 10" Oak S 0° 44.45'  
D-13, Leighton Twp. West 50.0'



Signed by Robert J. Jonker  
Surveyor's Michigan License No. Robert Jonker 21572

Date 4-4-97

LIBER 0006 PAGE 242