

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan County
(County)

Located in:
Wayland Twp.

Corner Code #

- | | | |
|---------------------------------------|--------------------------|----------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>11W</u> | <u>E-13</u> |
| | T _____ R _____ | <u>SE Cor. Sec32</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTERED
ALLEGAN COUNTY

97 JAN 22 11 1:29

FILLER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on July 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

80.00 ch. set corner post 32 & 33
Elm 16 N53E 172
Maple 9 N81W 14

Wightman Moored - 1987, used, no witnesses, show jog of 84.48'
also old notes, no date, stone
18" red Oak W 50'
8" Hickory NW 58'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike 2.5' South of C/L of E-W paved road (124th Ave.)
Removed & replaced with standard 3/4"x24" Allegan County capped monument.

Accepted as a careful & faithful reestablishment of the position of the original corner.
Approved by the Allegan County Remonumentation Peer Group on Nov. 26, 1996.

D-13, T3N, R11W, West 2610.88'
F-13, T3N, R11W, East 2672.76'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-24-96
COUNTY REP. Paul J. Van Oort

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Allegan County Monument

Nail & spike W-NW side P.Pole N32°E 31.13'
Nail & tag East side 16" tree S42°W 55.81'
Nail & tag South side P.Pole S63°E 72.98'
NE cor. Sec. 5, Martin Twp., East 84.48'

Nail & tags are Allegan Co. Remon. tags.



Signed by Robert J. Jonker Date 11-25-96
Surveyor's Michigan License No. 21572