

**SURVEY &
REMONUMENTATION**

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corner in **SECTION**

<u>Allegan Co.</u> (County)	Located In: Wayland Twp.	Corner Code # F-1
1. Public Land Survey	T <u>3N</u> R <u>11W</u>	<u>✓</u> F-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Robert J. Jonker

98 JAN 21 PM 1:38

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert J. Jonker, in a field survey on 01-03, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		11		12		13		14		15	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
Not set in G.L.O. survey

Jonker Land Surveys, 1987
Set point on the twp. line 6.54' West of the standard corner by extending line North from the center of the section and thru the East line of the Plat of "Grant Park", in the SE $\frac{1}{4}$ of the NW $\frac{1}{4}$ of Section 4, T3N, R11W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found $\frac{1}{2}$ " Jonker capped rered by 1987 survey in "A" above
The witnesses are the same as in "C" below.


The position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Peer group approved April 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Allegan County monument
Found Sq. spk. N. side 14" Maple N 90° W 14.88'
Found Sq. spk. W. side 10" Maple N 35° E 14.28'
Found Sq. spk. E. side 9" W.Cherry S 30° W 20.73'
F-13, Leighton Twp., East 6.54'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-8-97
COUNTY REP. K.V.O.



Signed by Robert J. Jonker
Surveyor's Michigan License No. 20572

Date 12-15-97