

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan County</u> <small>(County)</small>	Located In: Wayland Twp.	Corner Code # E-13
1. Public Land Survey	T3N R11W	S $\frac{1}{2}$ Sec. 33
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

97 JAN 22 PM 1:29
REGISTER OF DEEDS
ALLEGAN COUNTY
REGISTER OF DEEDS STAMP & FILE NUMBER
FILED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	25	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on July 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

AT 40 chains set quarter section post
Birch 9 N67 $\frac{1}{2}$ E 18
Do 8 N6 $\frac{1}{2}$ W 43

Old witnesses from Wightman Moored in Allegan - no date, stone, jog of 79.2' East to Martin corner.

6" Oak NE 54'
B. Walnut 6" NW 60.5'

Wightman Moored - 1987 - set R.R. spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike on C/L E-W paved road (124th Ave.) at C/L of 7th St. to the North.
Found Martin Twp. corner East 79.19' (recorded 79.2')

Accepted as a careful & faithful perpetuation of the position of the original corner.
Approved by the Allegan County Remonumentation Peer Group on Nov. 26, 1996.
E-13, T3N, R11W, West 2672.76'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-26-96
COUNTY REP. Robert J. Jonker

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced R.R. spike with standard Allegan County monument (3/4"x36" pin & cap).

NE corner of Orchard Hills Golf Course metal sign post S 9°W 52.55'
Nail & tag in E side 36" Tri-Aspen S12°E 39.42'
C/L top railroad rail fence post N58°E 56.15'
N 1/4 corner Section 4, Martin Twp., East 79.19'

Nail & tag is an Allegan Co. Remon. tag.

Signed by Robert J. Jonker Date 11-25-96
Surveyor's Michigan License No. 21572

