

REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

(County)	Located In:	Corner Code #
	Wayland Township	
1. Public Land Survey	T 3N R 11W	✓ G-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:38
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Robert J. Jonker

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert Jonker, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:


G.L.O. survey 1831
 Int. N. line 7 links (4.62') West of standard corner

Ratekin - 1973
 Sec. 33 Leighton, S $\frac{1}{4}$ -SE 2639.7'

Old notes of Ratekin & prior county surveyors show G.L.O. jog - corner never reset

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set point on twp. line 4.62' West (7 links) of std. corner.



Accepted as a careful and faithful reestablishment of the position of the original corner.

Peer group approved April 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Allegan County capped monument.
 Found Allegan Co. Remon Nail & Tag NW side 10" Maple N 70° E 8.55'
 Set Allegan Co. Remon Nail & Tag S'yly side 12" Maple N 20° W 18.07'
 Set Allegan Co. Remon Nail & Tag N. side 10" Maple N 70° W 12.92'
 Set Allegan Co. Remon Nail & Tag W. side 16" Tw.Maple S 0° 25.41'
 G-13, Leighton Twp. East 4.62'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-8-97
 COUNTY REP. K.V.O.

Signed by Robert J. Jonker
 Surveyor's Michigan License No. 21572

Date 4-4-97