

APR 07 1998

SECTION

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In: Wayland Twp.	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>11W</u>	✓ H-1
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
	T <u>    </u> R <u>    </u>	_____
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	_____
	S <u>    </u> T <u>    </u> R <u>    </u>	_____

98 JAN 21 PM 1:38

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on Nov. 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Not set in G.L.O. Surveys  
No info on record found in remon. research

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set point on township line on line fence & brush row to South  
12.82' West of Leighton Township corner.

Accepted as the best available evidence of the position of the corner:

Peer group approved April 8, 1997.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Allegan County capped monument on township line.  
Set Allegan County remon nail & tag S side 12" fence post      N85°E 11.68'  
Set Allegan County remon nail & tag W side 6" tw. Oak            S0°E 21.59'  
Set Allegan County remon nail & tag S side 8" Maple            N70°W 5.05'  
H-13, Leighton Twp. East 12.82'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 4-8-97  
COUNTY REP. K.V.O.

Signed by Robert J. Jonker  
Surveyor's Michigan License No. Robert Jonker P.S. 21572

Date December 15, 1997