

SURVEY & REMONUMENTATION

APR 29 1996
COMMISSION


ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

For corners in	Located in:	Corner Code #
Allegan (County)	Wayland Township	
1. Public Land Survey	T 3N R 11W	H-2
	T R	Center of
	T R	Section 3
	T R	Wayland
	T R	Township
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

1995 DEC 29 PM 4:05
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
Register of Deeds Stamp & File Number

FILED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, Chris Marschall, in a field survey on March 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|-------------------------------|----------------------------|------------------------------------|
| Old notes (No dates) | 1" Iron | 1981 Exxel |
| B. Walnut 5 N28°E 62 1/2' | T.P. SE 61.8' | T.P. SSE 61.3' |
| B. Walnut 20 NE 40.5' | 14" Walnut ESE 55.6' | 14" Walnut SE 55.6' |
| B. Walnut 3 SE 43.1' | RR Tie Fence Post N 23.85' | RR Tie Fence Post N 23.85' |
| W 1/4 Cor. West 39.82 Ch. | St. Sign NW 24.14' | Street Sign NW 24.14' |
| E 1/4 Cor. East 39.94 Ch. | 28" Cherry SW 73.0' | |
| E-W 1/4 Line Mag. Var. 4° 33' | W 1/4 Cor. West 2635.90' | This corner was not set by the GLO |
| | E 1/4 Cor. East 2635.90' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4 Solid Iron in Monument Box at the intersection of 135th Avenue and 5th Street. This Location appears to fit with the Center of Section held for all recorded surveys to date.

APPROVED BY ALLEGAN COUNTY PEER GROUP DATE 4/11/95

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | | |
|---|--------------|----------|
| Standard Allegan County Red Remon Cap set over existing Iron Pin | | |
| N 1/4 Cor. | N 01°40'09"E | 2615.11' |
| S 1/4 Cor. | S 00°29'43"W | 2702.31' |
| E 1/4 Cor. | S 89°47'01"E | 2631.69' |
| W 1/4 Cor. | N 89°45'51"W | 2635.31' |
| Center of Section is 0.45' S and 27.13' W of the intersection of the 1/4 lines. | | |
| Nail & Allegan Co. Remon tag in S-side PP 6' High | N79°W | 141.28' |
| Nail & Allegan Co. Remon tag in S-side PP | N72°E | 164.01' |
| Nail & Allegan Co. Remon tag in NW-side PP | S43°W | 199.12' |
| Nail & Allegan Co. Remon tag in W-side 10" Bitter Hickory | S05°E | 291.00' |
| Top SW corner old Stone Barn Foundation | N73°E | 211.49' |

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-11-95
COUNTY REP. Paul J. [Signature]

Signed by Chris Marschall Date March 23, 1995
Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971
REVISED MAY 24, 1978
REVISED JAN., 1983