

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In: Wayland Township	Corner Code # I-1
1. Public Land Survey	T3N R11W	I-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:38
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert Jonker, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831, Sylvester Sibley D.S.	I-1, 1972, W&W, Part A, stone (LCRC 1-400)
North between Sec. 2 & 3	30" Elm NW 63.2'
77.80 ch. intersects N line	6" Oak SE 27'
47 links West of post	Fe. post N 30'
B. Oak 6 75E 22	Part B - found solid iron
	Part C - took witnesses of
	18" Hick. E 23' NE cor. hse fnd. S68°W
	20" Hick. W 6.37' 91.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" solid iron per witnesses of Part "C" of LCRC 1-400.



Accepted as the best available evidence of the position of the original corner.

Peer group approved April 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard Allegan County monument on Twp. line
 H-13, T4N, R11W, East 31.02'
 Iron West on Kalamazoo Road 247.45'
 NE corner house fndn. S 68° W 91.65'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-8-97
 COUNTY REP. K.V.O.

Signed by Robert J. Jonker
 Surveyor's Michigan License No. Robert Jonker 21572

Date 4-4-97