

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
For corners in

<u>Allegan</u> (County)	Located in: Wayland Twp.	Corner Code # I-4
1. Public Land Survey	T3N R11W	✓ I-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Robert J. Jonker*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

98 JAN 21 PM 1:38

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on 8-27, 1994 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration: (no date)

1831 Sylvester Sibley D.S.	E½ of 10 Iron, old notes	old old notes
North between Sec. 10 & 11	Steel ice post S. 33'	STONE
40.00 ch Set ¼ post	St. sign SSW 24'	Oak 16 NW 64'
Maple 30 N73W 25	T. pole S. 46.5'	? 10 NW 50'
W. Oak 7 N71E 15	22" Cherry SW 73.2' cks.1994	
	T. pole NW 71.7'	
	22" Cherry NW 83.4' cks.1994	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike @ grade, raised over ½"x16" rerod 4" below grade  
Rerod was over large stone 13" below grade.



Accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved Dec. 30, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with std. 24" capped Allegan County monument angled over large stone.  
Allegan County Remon Tag & Nail - SE side 18" Walnut Az. 40° 63.15'  
Allegan County Remon Tag & Nail - E. side 32" W.Cherry Az. 340° 83.95'  
Allegan County Remon Tag & Nail - NE side 15" Pine Az. 140° 39.40'  
Allegan County Remon Tag & Nail - N. side 36" W.Cherry Az. 240° 73.71'  
on C/L BT to North & 1' South of C/L E-W BT.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-30-97  
COUNTY REP. K.V.O.

Signed by Robert J. Jonker  
Surveyor's Michigan License No. 21572

Date 12-15-97