

**SURVEY &
REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Allegan</u>	Located In:	Corner Code #
(County)	Wayland Twp.	
1. Public Land Survey	T <u>3</u> N R <u>11</u> W	✓ J-1
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

98 JAN 21 PM 1:38
FILED
Robert J. Jonker
REGISTERED IN 1992
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on 02-03, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Not set in GLO survey. LCRC #1-399 - 1972, W & W
Part B - "T" iron set at fence corner
Part C - Took witnesses
18" Maple S 57° W 22.7'
18" Maple N 33° W 27.85'
24" Oak N 90°00'E 33.39'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1986 look for corner - not in - reset from witnesses listed in "A" above for LCRC #1-399 - set capped rerod.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-8-97
COUNTY REP. K.V.O.

Accepted as the best available evidence of the position of the corner.


Peer group approved April 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4"x2' std. Allegan County capped monument
Allegan County Remon Tag & Nail SW side 28" Maple N 28° W 26.39'
Allegan County Remon Tag & Nail NW side 8' Poplar N 52° E 35.19'
Allegan County Remon Tag & Nail N. side 6" Box Elder S 82° E 10.52'
Allegan County Remon Tag & Nail N. side 10" Ask S 50° E 18.78'
J-13, T4N, R11W, East 34.43'

Signed by *Robert J. Jonker*
Surveyor's Michigan License No. 21572

Date 12-15-97



FILED 0006 PAGE 257