

**SURVEY & REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**  
For corners in

<u>Allegan</u> (County)	Located In: <u>Wayland Twp.</u>	Corner Code # <u>1 K-2</u>
1. Public Land Survey	T <u>3</u> N R <u>11</u> W	<u>1</u> K-2
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

98 JAN 21 PM 1:38  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*James A. Batters*

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on 12-27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831, Sylvester Sibley LCRC #1-398 - W&W, 1972  
North between Sec. 1 & 2 Part A-10" Tamarack NE 24 1/2'  
40.00 ch. set 1/4 post Part B-Set T iron on c/l  
Pine 7 N62W 20 roads N & S & W  
Maple 9 S35E 15 Part C-Took witnesses  
16" Maple S33°E 24.88'  
8" Maple S35°W 56.10'  
12" Maple N25°W 58.8'

LCRC #4-37, Jonker, 1988  
Part B-reset corners from W&W info.  
Part C-Took witnesses  
Nail NE side 18" Maple S30°E  
Nail N. side 30" Maple N65°E 65.69'  
Nail N. side 16" Elm S80° W 19.91'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Jonker capped rod by witnesses listed in "A" above for LCRC #4-37, part "C".

Road has been raised about 3'


APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 4-8-97  
COUNTY REP. R.V.O.

Accepted as the best available evidence of the position of the original corner.

Peer group approved April 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4"x36" std. Allegan Co. Mon.  
Found Nail on N. side 36" Maple N 70° E 65.62'  
Found Nail on N. side 10" Maple S 45° E 51.06' - A.C. tag  
Set Nail on E. side 17" Maple S 30° W 66.03'  
Set Nail on S. side 26" Maple N 75° W 55.94'



Signed by Robert J. Jonker  
Robert J. Jonker PS  
Surveyor's Michigan License No. 21572

Date Dec. 30, 1997

LINE# 0006 PAGE 259

Over for Sheet 2

Part "A" (Cont'd)

1993 - Excel Eng. Found Iron - no witnesses