

**SURVEY &
REMONUMENTATION**

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

**APR 29 1996
COMMISSION**

For corners in
Allegan
(County)

Located in: Corner Code #

1. Public Land Survey	T <u>3N</u> R <u>11W</u>	<u>K-13 (SW, 36)</u> <u>Wayland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1995 DEC 14 PM 2:40
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5					3	2	1			
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on July 9, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 K-13 John Mullett, D.S.
 Jan. 21, 1826
 Set cor.
 Birch 16" N 55° W 34'
 Birch 16" N 42 1/2° E 46'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 K-13 Found 1/2" iron in Mon. Box
 And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-14-95
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-13 Replaced 1/2" iron w/Allegan Co. Mon. (3/4" x 24" pin w/cap) in Mon. Box
 Nail & Allegan Co. Remon. Tag in N side PP N 80° W 183.79'
 Nail & Allegan Co. Remon. Tag in N side PP S 25° E 22.88'
 Nail & Allegan Co. Remon. Tag in S side PP N 80° E 200.65'
 NE cor. conc. porch hse. #214 S 65° W 187.19'
 C/L bit. E-W, North 1.5'±; on tree line North
 NW cor. 1 2-11 East 59.68'

Signed by John C. Bueche Date Oct 2, 1995
 Surveyor's Michigan License No. 13027

