

**SURVEY & REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corner in **SECTION**  
Allegan  
(County)

Located in: Wayland Twp. Corner Code # L-1  
T 3N R 11W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

98 JAN 21 PM 1:39  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*James A. ...*

FILED

Register of Deeds Stamp & File Number

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on July 03, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET IN GLO SURVEY Old 1875 sketch by Hicks shows location @ midpoint of mile. (no date) Per Ratekin sketch - shows jog of 20.65', point in @ midpoint of mile, and distances of 2674.32' to NW & NE corners of section

LCRCH, L. 4, P.37, Jonker, survey of 11-24-87, Set 1/2" capped rerod on twp. line Set corner @ midpoint of mile per Wightman-Moored info. Took witnesses: Nail W. side 28" Oak S 33° W 40.56'; PK Nail S. side p. pole N40°W 45.49' Nail E. wide 10" Oak S 9° E 38.32'; 3/4" pin in mon box East 20.65'

(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped rerod per witnesses from LCRC # per L. 4, Pg. 37.


APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 7-8-97  
COUNTY REP. K.V.O.

Accepted as the best available evidence of the position of the corner.

Peer group approved July 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced capped rerod with 3/4" x 24" standard capped Allegan County monument.

Found nail on W. side 28" Oak S 33° W 40.56'  
Found nail on E. side 10" Oak S 9° E 38.32'  
Found PK nail S. side p. pole N 40° W 45.49'  
L-13, T4N, R11W, East 20.65'



Signed by Robert J. Jonker Date 12-15-97  
Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1993

Part "A" (cont'd)

L-1, T3N, R11W

Old notes of Oct 19, 1875 survey, page 73 (Hicks)  
Set  $N\frac{1}{4}$  (L-1)  
Mile = 81.04 chains  
Set  $\frac{1}{4}$  post @ 40.52 ch.

1979 survey - J. Dillingham, L. 957, Pg. 308  
Held straight line NW to NE corner section  
no mention of  $N\frac{1}{4}$  Corner