

SURVEY &  
REMONUMENTATION

APR 29 1996  
COMMISSION

Alleghan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
Alleghan (County)		
1. Public Land Survey	T <u>3N</u> R <u>11W</u>	<u>L-13 (S1, 36)</u> <u>Wayland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 1995 DEC 14 PM 2:40  
 REGISTER OF DEEDS STAMP & FILE NUMBER  
 FILED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on July 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |                     |             |                             |
|---------------------|-------------|-----------------------------|
| L-13 GLO Jan., 1826 | Old records | LCRC L2, P138, 1972 Ratekin |
| John Mullett, D.S.  | Stone       | Iron bent over              |
| Set post            | B. Walnut   | Nail in PP N 34.05'         |
| B. Oak 10 N 68 E 37 | 10" SE 58'  | Nail in PP (E. Pole)        |
| Beech 10 N 30 W 28  | 6" Hickory  | S 45 W 58.80'               |
|                     | N 48.4'     | SW cor. of cor. fence       |
|                     |             | post S 60 E 45.88'          |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- L-13 Found 3/4" solid iron in Mon. Box (no cover)

Nail in PP N 34.05'±  
 Nail in PP E. Pole  
 S 45 W 58.80'±

And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 8-14-95  
 COUNTY REP. [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Left 3/4" solid iron in Mon. Box; placed Alleghan Co. Cap on iron (no cover on box)  
 Nail & Alleghan Co. Remon. Tag in N side PP S 65 W 71.94'  
 NW cor. metal bldg. S 45 E 116.58'  
 SW cor. metal bldg. N 60 E 205.03'  
 SW cor. West end of metal bldg. N 10 E 137.64'  
 On C/L bit. E-W; on tree row North  
 Alleghan Co. Mon. N 1/4 cor. 1, 2-11, East 33.75'



Signed by John C. Bueche  
 Surveyor's Michigan License No. 13027

Date Oct 2, 1995