

SURVEY & REMONUMENTATION

APR 07 1998

Allegan County Remonumentation

SECTION

For corners in

Allegan
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located in: Corner Code #

- 1. Public Land Survey
T3N R 11W ✓ M-5 (SE 12)
T R Wayland Twp.
- 2. Property Controlling in Section
S T R
- 3. Miscellaneous Property in Sec.
S T R

98 JAN 21 PM 1:39
REGISTER OF DEEDS
ALLEGAN COUNTY MI

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Steven Koerber, in a field survey on Oct. 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- M-5 GLO - John Mullett DS, 1826 1. A Gardner May 1, 1879 2. Old notes from Wightman 5-9-1978
W. Oak 11 S61W 38 Stone set 1" iron at Govt. jog distance between
Do. 13 N15W 26 no wits NW corner Sec 18 Yankee Springs and
West 1/4 post sec. 7 Yankee Springs
Nail in N. side P. pole West 51.75'
Nail in NE side 18" Hickory S30W 54.95'
C/L road East 1.5'
NW corner sec. 18-3-10 South 100.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5 Found 1" solid Iron rod in Mon. Box
Fnd. Pk in N. side P. Pole West 51.60'
Nail in NE side 18" Hickory S30°W 54.95'
C/L road 1.5' East
M= 100.24' to A-3 (NW corner Sec. 18-3-10 Barry County)

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-11-97
COUNTY REP. K.V.O.

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer Group approval November 11, 1997.
Dist to M-4 = 2648.98'
Dist to M-6 = 2645.74'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 Set Standard Allegan Co. Mon. (3/4" x 24" Iron Rod with Remon. cap)
Set nail & Allegan Co. Remon. tag in NW side 22" Hickory S35°W 55.40'
Set nail & Allegan Co. Remon. tag in N. side P. Pole West 51.55'
Set nail & Allegan Co. Remon. tag in W. side 10" Sassafras S20°E 105.14'
Set nail & Allegan Co. Remon. tag in W. side 24" Walnut N10°W 142.49'
C/L Patterson road 1' East



Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 12-18-1997

LIB# 0006 PAGE 271

M-5 WAYLAND TWP.

3. 5-15-1978
John Dillingham
Act 132 recorded survey L. 941, Pg. 778
1" Iron
Nail in N side P. Pole West 51.75'
Nail in NE side 18" Hickory S30W 54.95'
NE corner Sec. 18 Yankee Spr. Twp. South 100.32'
C/I road East 1.5'
4. 2-2-1984
Ray Moorcd
Act 132 recorded survey L. 1099, Pg. 768
5. 4-4-1983
L.C.R.C. L 3, Pg. 386 (Alleghan Co.)
Robert Jonker
Found 1" steel pin
¾" rd iron South 100.3'
Ratekin capped iron W. 33.06'
Nail & tag on E. side 22" Hickory S35W 54.96'
6. 4-19-1983
Robert Jonker
Act 132 recorded Survey L. 1061, Pg. 300
Same wits as in No. 5