

APR 07 1998

Allegan County Remonumentation

**SECTION**

For corners in

Allegan

(County)

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Located in:

Corner Code #

- |                                       |   |                  |
|---------------------------------------|---|------------------|
| 1. Public Land Survey                 | T <u>3N</u> R <u>10W</u>                  | ✓ M-6 (E 1/4 13) |
|                                       | T <u>    </u> R <u>    </u>               | Wayland Twp.     |
|                                       | T <u>    </u> R <u>    </u>               |                  |
|                                       | T <u>    </u> R <u>    </u>               |                  |
| 2. Property Controlling<br>in Section | S <u>    </u> T <u>    </u> R <u>    </u> |                  |
|                                       | S <u>    </u> T <u>    </u> R <u>    </u> |                  |
| 3. Miscellaneous<br>Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> |                  |
|                                       | S <u>    </u> T <u>    </u> R <u>    </u> |                  |

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

98 JAN 21 PM 1:39

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on Oct. 14 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970; the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |     |   |                          |    |   |
|-----|---|--------------------------|----|---|
| M-6 | GLO - John Mullett DS, 1826   | 1. A Gardner May 1, 1879 | 2. | Old notes from Wightman 5-9-1978          |
|     | B. Oak 7 S10W 42  | Stone with "X"           |    | set 3/4" Pipe to replace 1/2" rcf. Rod on |
|     | W. Oak. 14 N37W 41  | no wits                  |    | stone with 'X'                            |
|     |   |                          |    | P.K. nail w/ washer in root of hickory    |
|     |   |                          |    | WSW 85.25'                                |
|     | (Additional info. on back of sheet)   |                          |    | P.K. nail w/ washer in p.pole NNE 85.30'  |
|     |   |                          |    | P.K. nail w/ washer in Hickory NW 40.26'  |
|     |   |                          |    | St. sign SW 43.97' (revised S35°W 45.25') |
|     |   |                          |    | 40.12 CH West to Center of Section        |
| B.  | Description of corner evidence found and/or method applied in restoring or reestablishing corner: |                          |    | C/L road East 5' on C/L road W.           |

- M-6 Found 3/4" iron pipe in Mon. Box  
C/L road 5' East  
Face of corner fence post S45°W 51.1'  
Nail in 14" Hickory S15°E 96.6'  
M= 114.95' South to A-6 (W 1/4 corner Sec 18-3-10 Barry County)  
This corner is accepted as a careful and faithful perpetuation of the position of the original corner.  
Peer Group approval November 11, 1997.  
Dist to M-5 2645.74'  
Dist to M-7 2658.56'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-11-97  
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 Set Standard Allegan Co. Mon. (3/4" x 24" Iron Rod with Remon. cap)  
Set nail & Allegan Co. Remon. tag in E. side P. Pole N20°W 84.51'  
Set nail & Allegan Co. Remon. tag in E. side RR tie fence post S40°W 56.67'  
Set nail & Allegan Co. Remon. tag in SE side 14" Hickory S25°E 96.56'  
South leg traffic sign S75°E 26.8'  
C/L 131' Avenue to West 1' South  
C/L Patterson Road 4.5' East  
A-6 (W 1/4 corner Sec 18-3-10 Barry County) 114.95' South

Signed by S. C. Koerber  
Surveyor's Michigan License No. 39065

Date 12-13-1997



## M-6 WAYLAND TWP.

3. 5-15-1978  
John Dillingham  
Act 132 recorded survey L. 941, Pg. 778  
¾" Pipe  
Street sign S35°W 45.25'  
C/L road East 5' - on C/L road to West  
Nail in 10" hickory S15°W 78.83'  
Nail in corner fence post S45°W 51.16'  
Nail in Power Pole N20°E 85.70'
4. 11-28-1977  
L.C.R.C. Liber 3, Pg. 174  
Douglas Bonnema  
¾" iron Pipe  
PK nail in NE side T. pole NW 59.42'  
Nail & tag in NE side 12" Hickory SE 96.66'  
Pk nail & washer in root 18" Hickory W-SW 85.25'  
PK nail in P. Pole N-NE 85.30'  
Iron @ W ¼ corner Sec. 18-3-10 South 115.0'
5. 6-5-1981  
Act 132 survey L. 1009, Pg. 420  
Robert Jonker  
¾" rd. iron  
P.K. on NE side T. pole NW 59.42'  
N&T on NE side 12" Hickory SE 96.60'  
P.K. on P. Pole NNE 85.30'  
Iron- West ¼ cor. Sec. 18-3-10 S 115.0'
6. 2-2-1984  
Ray Moored  
Act 132 recorded survey L. 1099, Pg. 768  
Wits same as No. 3 above
7. 8-11-1986  
Act 132 survey  
Robert Jonker  
1" Iron  
Nail in W. side P. Pole N25°E 85.70'  
Nail in NE side fence post S45°W 51.43'