

SURVEY & REMONUMENTATION

APR 07 1998

Allegan County Remonumentation

SECTION

For corners in

Allegan
(County)

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Corner Code #

- | | | |
|------------------------------------|------------|----------------------------------|
| 1. Public Land Survey | T 3N R 11W | ✓ M-8 (E 1/4 24)
Wayland Twp. |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

98 JAN 21 PM 1:39
REGISTER OF DEEDS
ALLEGAN COUNTY MICH
Steven C. Koerber
FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Steven Koerber Oct. 14 1997
I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|--|--|
| M-8 GLO - John Mullett DS, 1826
W. Oak 11 N31½°W 22
Do. 18 S56W 406 | 1. Co. Surveyor notes July 31, 1874
Dist to SE corner sec. 24
is 40.09½ ch. (2646.27') | 2. H. Mac Dougall Nov. 6, 1913
Stake & Stone
Oak 4 NW 53'
Oak 12 SW 36.8' |
|---|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8 Found P.K. nail
Dist to M-9 (SE 24) = 2647.90'
Dist to A-8 (W ¼ 19-3-10) = 102.86'

APPROVED REMONUMENTATION CORNER
DATE APPROVED 12-9-97
COUNTY REP. K.V.O.


This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer Group approval December 9, 1997.
Dist to M-7 = 2645.80'
Dist to M-9 = 2647.90' Old note dist (1874) = 2646.27'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8 Set Standard Allegan Co. Mon. (3/4" x 24" Iron Rod with Remon.cap)
Set nail & Allegan Co. Remon. tag in NW side Guy pole S35°W 89.75'
Set nail & Allegan Co. Remon. tag in E. side 8" Pine N45°W 94.97'
Set nail & Allegan Co. Remon. tag in E. side 8" Pine N30°W 86.52'
Stop sign post S80°W 46.5'
C/L Patterson Road 0' East
C/L Bituminous drive to West 6' North
A-8 (W ¼ 19-3-10 Barry County) 102.86' South

Signed by *Steven C. Koerber*
Surveyor's Michigan License No. 39085

Date 12-18-1997



REP 0006 PAGE 277

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT, 1985

M-8 WAYLAND TWP.

3. L.C.R.C. No. 405 (Barry Co.) Jan. 10, 1990 A-8 (W ¼ corner Sec. 19-3-10) Barry Co.
½" solid iron 1.58' W. of Twp. Line
N&T SE side 12" Oak S20°W 92.60'
PK nail NE side P. Pole N60°W 54.07' (found)
PK nail NE side P. Pole S45°E 56.25' (found)
PK nail on Twp. Line N 102.80'
4. Pleasant Valley Plat Sec. 19-3-10
Plat Dist= 206.0' South from W ¼ corner Sec. 19
Meas. Dis.= 205.77' from W ¼ corner Sec. 19