

**SURVEY & REMONUMENTATION**

APR 29 1996

COMMISSION

**Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code
<u>Allegan</u> <small>(County)</small>		
1. Public Land Survey	T <u>3N</u> R <u>11W</u>	<u>M-11 (NE, 36)</u> <u>Wayland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:41  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.  
 REGISTER OF DEEDS STAMP & FILE NUMBER

FILED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on July 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 GLO, 1826	Survey L	, P	Survey L1, P543, Barry Co.
John Mullett, D.S.	1 1/4" iron pin		3/4" iron, Oct., 1979 Ratekin
Set post	in Mon. Box		Nail E side PP N 20 W 103.15'
R. Oak 19	PP S 40 W 42.85'		T iron SW cor. Sec. 30, 3-10 S 82.
S 54 W 40	20" Oak N 65		SW cor. Texaco sign fnd. N 50 W 65
W. Oak 19	E 50.30'		Spk. S side P&T pole S 40 W 43.41'
N 62 W 98	16" Oak N 35		SW cor. hse. fnd. N 40 E 122.76'
	E 58.80'		Same as LCRC L3, P148

OVER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found 1 1/2" x 12" solid iron Mon. Box.

PP S 40 W 42.85'	Spk. S side P&T pole S 40 W 43.41'
16" Oak N 35	SW cor. hse. fnd. N 40 E 122.76'
E 58.80'	T iron SW cor. Sec. 30, 3-10 S 82.

And is accepted as a careful and faithful perpetuation of the position of the original corner.


APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 8-14-95  
COUNTY REP. John C. Bueche

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Replaced solid iron w/Allegan Co. Rod (3/4" x 24" w/Cap)  
 Conc. Nail & Allegan Co. Remon. Tag in E side PP S 45 W 42.85'  
 Conc. Nail & Allegan Co. Remon. Tag in W side Guy Pole S 30 E 40.87'  
 Conc. Nail & Allegan Co. Remon. Tag in SE side 22" Oak N 40 E 59.35'  
 SW cor. hse. fnd. N 40 E 122.76'  
 Barry Co. Mon. in Mon. Box, SW cor. 30, 3-10 South 82.04'  
 C/L bit. N-S, W 2'±  
 C/L bit. W, S 1'±

Signed by John C. Bueche  
 Surveyor's Michigan License No. 13027

Date Oct 2, 1995



## PART A - continued

Jonker, 1985, 9-89  
1 1/4" iron pin  
PP S 40 W 42.85  
20" Oak N 65 E 50.3  
16" Oak N 35 E 58.8  
SE cor. conc. sign base N 45 W 64.15  
Same as LCRC L1, P24  
Tri-Co. Land Surveys, 2-86  
Same as L001, P543  
Jonker, 9-89  
1 1/4" iron in Mon. Box