

SURVEY & REMONUMENTATION

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APR 29 1996

COMMISSION

For corners in <u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>11W</u>	<u>M-12 (E1, 36)</u> <u>Wayland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1995 DEC 14 PM 2:41
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

I, John C. Bueche, in a field survey on July 9, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 GLO, Jan., 1826	Old notes	Survey L _____, P _____
John Mullett, D.S.	Ash stake	June, 1985
Br. Oak 7 for cor.	Swamp Oak 15" N 10	T iron
	Swamp Oak 13" N 67	SE cor. metal bldg. S 40 W 44.00'
		NE cor. metal bldg. S 70 W 27.26'
		NW cor. garg. (conc. fnd.)
		hse. #3525 S 35 E 182.68'
		Same as other wit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-12 Found T iron
As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner and has been used as a common corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 8-14-95
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Replaced T iron w/Allegan Co. (3/4" x 24" Pin w/Cap)
NE cor. metal bldg. S 70 W 27.76'
SE cor. metal bldg. S 40 W 43.98'
SW cor. metal bldg. N 55 E 87.35'
NW cor. base for CP box S 60 E 105.34'
At fence cor. S & W (10'± long)
C/L bit. N-S, East 15'±



Signed by John C. Bueche Date Oct 2, 1995
 John C. Bueche, P.S.
 Surveyor's Michigan License No. 13027