

SURVEY & REMONUMENTATION

APR 25 1995

Allegan County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

<u>Allegan Co</u> <small>(County)</small>		Located In: <u>Hopkins Twp.</u>	Corner Code # <u>A-2</u>
1. Public Land Survey	T <u>3N</u> R <u>12W</u>	<u>A-2</u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

1994 DEC 30 PM 12: 1

REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

Register of Deeds Stamp & File Number

FILED

I, Robert Jonker, in a field survey on August 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	31	32	33	34	35	36						
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Not set in G.L.O. survey

Liber 811, Pg. 451-453 of Surveys
Iron (Russ Donker, 1972)

Corner common with T3N, R13W corner

24" Ash N 28.2'
12" Maple WSW 70.9'
Fce. post SSE 32.0'

LCRC - Liber 3, Pg. 348
Jonker, 1982

Found 1" solid bar by wit. listed to left

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" solid bar, by LCRC listed in "A" above.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 9-13-94
COUNTY REP. Richard L. Carter


This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Peer Group approved on 9-13-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced solid bar with 36" standard Allegan County capped monument.

A.C. Tag, W. side 12" Ash Az. 150° 31.72'
A.C. Tag, NW side 22" Maple Az. 243° 71.44'
A.C. Tag, E. side 36" Ash Az. 0° 28.96'
A.C. Tag, E. side 9" Maple Az. 60° 50.12'



Signed by Robert J. Jonker
JONKER LAND SURVEYS, P.C. 21572
Surveyor's Michigan License No. _____

Date 12-2-94

0005 PAGE 090