

REMONUMENTATION

APR 25 1995

Allegan County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
 For corners in

<u>Allegan Co.</u> <small>(County)</small>	Located In: Hopkins Twp.	Corner Code # A-3
1. Public Land Survey	T <u>3N</u> R <u>12W</u>	A-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1994 DEC 30 PM 12:15
Gregory A. LeBeau

FILED

Register of Deeds Stamp & File Number

I, Robert Jonker, in a field survey on August 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey, 1831, West between Sections 6 & 7, 1980, Nederveld & Assoc.
 intersects West boundary @ post @ 80.0 chains R.R. spike, found

GLO survey, 1831, North, 80 chains, set post,
 to Sec. 1 & 12, T3N, R13W,
 W. Oak 24" S 47° W 22 links 1982, Jonker, LCRC #3-348, Fd. R.R. spk.
 Pine 8" N 37° W 55 links Reset with 3/4" capped iron

1982 cont'd: C/L top steel fc. cor. post Nail NE side 12" Oak S 50° E 58.23'
 S 0° 40.74' on old fce. & tree line to N. Nail W. side 24" Ash S 10° E 35.63'
 & fce. line to S., & C/L gravel is 9' S. Nail SE side 28" Oak S 45° W 49.27'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" capped iron as per LCRC #3-348
 Corner is common with T3N, R13W


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 9-13-94
 COUNTY REP. *Robert J. Jonker*

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard 3' long Allegan County capped monument.

A.C. N&T	N. side 18" Oak	Az. 130°	58.08'
A.C. N&T	W. side 30" Tree	Az. 170°	35.63'
A.C. N&T	SE side 32" Oak	Az. 235°	49.38'
A.C. N&T	NW side 26" Oak	Az. 250°	62.80'
C/L	top steel fence post	Az. 180°	40.9'



Signed by Robert J. Jonker
 JONKER LAND SURVEYS, P.C. 21572
 Surveyor's Michigan License No.

Date December 28, 1994