

Allegan County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

FILED  
 1995 DEC 14 PM 2:33  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN

For corners in  
Allegan  
(County)

Located In: Hopkins Twp. Corner Code # B-2

1. Public Land Survey	T	R	
	T	R	<u>3N 12W</u>
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

APR 29 1996

**COMMISSION**

Register of Deeds Stamp & File Number

I, Robert Jonker, in a field survey on August 20, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	●	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessions and/or subsequent restoration:  
 This position not established by original government surveyors.

Surveys recorded by Russ Donker, 1972,  
 L.811, P.452 & 453  
 26" Maple S 27.6'  
 30" Maple N 28.6'  
 18" Maple SW 47.4'

Old wit. map, P.114, May 1, 1876  
 calls for a stone, blue triangular  
 39.73 ch. West of E 1/2 corner &  
 40.49 ch. North of S 1/2 cor. (J.W.Hic)

Used by Kistler & Assoc. 1978, Don Sandel  
 3/4" pipe - same wit., L.947, P.61

LCRC #3-349, Jonker, 1982  
 same wit. as surveys listed to the left

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3/4" pipe by wit. listed in "A" above.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.  
 I calculate the historical center to be 0.12' North of E-W 1/2 line and 0.3' West of N-S 1/2 line.


APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 12-14-95  
 COUNTY REP. R.V.O.

Peer Group approved on 12-14-95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced with 3' standard Allegan County monument.

..C. Tag E. side 33" Maple Az. 180° 29.20'  
 ..C. Tag NW side 36" Maple Az. 213° 33.50'  
 ..C. Tag W. side 35" Maple Az. 360° 30.12'  
 PK Nail E. side p.pole Az. 32° 49.31'  
 E-W centerline of gravel is 8' North

B-1, North, 2411.84'  
 B-3, South, 2657.8'  
 C-2, East, 2627.14'  
 A-2, West, 2580.5'



Signed by Robert J. Jonker  
JONKER LAND SURVEYS, P.C. 21572  
 Surveyor's Michigan License No. \_\_\_\_\_

Date October 11, 1994