

APR 29 1998

SECTION

ALLEGAN CO. REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan County

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T-3N R-12W	D-13
	T_____ R_____	S 1/4 SEC. 32
	T_____ R_____	HOPKINS TWP
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

FILED  
1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

LIBR00005 PAGE 49

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ARTHUR W. BRINTNALL, in a field survey on 27 AUG, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
WEST SOUTH SIDE SEC 32  
40.00 SET QR SEC COR ON SUGAR 9

APR 19, 1876 J.W. HICKS, C.S.  
- SURVEY IN SW 1/4  
- FROM S 1/4 COR RUN WEST 40.02 TO SEC COR

APR 29<sup>TH</sup>, 30<sup>TH</sup> & MAY 2<sup>ND</sup> 1887 E.P. WATERMAN, D.C.S.  
- "ESTABLISHED 1/4 POST ON S. LINE OF 32 BY ORIGINAL WITNESS AND PUT IN STONE X ON TOP X ON W SIDE"  
- SET STONE ON SEC LINE 17.555 CHS (1558.63') WEST OF S 1/4 POST  
- MEAS 40.01 (2640.66') WEST TO SW COR  
- MEAS 40.26 (2657.16') EAST TO SE COR  
- SKETCH CALLS FOR STONE & BRICK AT S 1/4 COR

CONTINUED ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1" IRON & BRICKS  
40 D NE SDE 24" MAPLE S30° E 26.31  
CENTER; LINE (W. SDE) 20" MAPLE S45° E 33.04  
40 D SE SDE 36" MAPLE S 50° W 45.15  
269°-47'15" 2640.44' TO C-13  
270°-00'-00" 2655.74' TO E-13

REPLACE 1" IRON WITH STD A.C. MON (3/4" X 24" IRON WITH CAP) AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

APPROVED BY ALLEGAN PEER GROUP 11 AUG 98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD A.C. MON (3/4" X 24" IRON WITH CAP) IN CENTERLINE 124<sup>TH</sup> AVE  
NAIL & REMON TAG NE SDE 20" MAPLE S45° E 33.06'  
NAIL & REMON TAG NE SDE 24" MAPLE S 30° E 26.27'  
NAIL & REMON TAG SE SDE 36" MAPLE S 50° W 45.21'  
NAIL & REMON TAG S'LY SDE 24" MAPLE N 75° E 58.84'  
CENTERLINE DR TO NORTH (HSE #2095) WEST 5'±  
D-1 (T-2N, R-12W) STD A.C. MON WEST 15.65'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED AUG 11, 1998  
COUNTY REP. [Signature]

Signed by Arthur W. Brintnall  
PREIN&NEWHOF  
Surveyor's Michigan License No. #28407

Date SEPT. 8, 1998

D-13 HOPKINS TWP.

A. CONT.

1966 D.A. RATEKIN, C.S.

- FD BRICKS SET 1" IRON
- 10" MAPLE NNW 25.3'
- 14" MAPLE SW 32.0'
- 24" MAPLE SW 44.5'
- 14" MAPLE SSE 25.4'
- 12" MAPLE SE 32.75'
- LINE OF MAPLES TO SOUTH WEST 79.5'
- FD STONE ON S. LINE WEST 1558.34'

NOV 17, 1977 D.A. RATEKIN, C.S.

ACT 132 SURVEY  
SAME WITNESSES AS ABOVE

JUNE 16, 1983 R.E. MOORED, P.S.

ACT 132 SURVEY  
SAME WITNESSES AS ABOVE

CIRCA 1980'S K.L. VAN ORDER, C.S.

SAME WITNESSES AS ABOVE

SURVEY  
REMONUMENTATION

APR 29 1983

SECTION

