

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
	Hopkins Twp.	
1. Public Land Survey	T <u>3</u> N R <u>12</u> W	<u>J-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 006 PAGE 52

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert J Jonker, in a field survey on 10-29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Not set in G.L.O. survey
No info. of value available from Tri County in 1983 (per Ray Moored)

Jonker-1983 set on line with Dorr Twp.-on occupation line of trees to the South

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DATE APPROVED NOV-10-1998
COUNTY REP. Mark J. Van Oort

Found Jonker capped 1/2" rerod
Replaced with 36" std. Allegan Co. Monument on twp. line

And is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Allegan County std. monument
A/C remon tag-SW. side 17" Maple N21°W 43.71'
SW Corner brick house foundation N33°E 84.91'
Found P.K. nail on W. side P. pole S50°W 101.05'
Found nail on W. side 10" tw. Elm S19°E 29.46'
J-13, Dorr Twp. West 7.88'
C/L E-W gravel road South 2'
on C/L Ditch to South



Signed by Robert J. Jonker
Surveyor's Michigan License No. 21572

Date 11-9-98