

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>Allegan</u> (County) | Located In: | Corner Code # |
| | Hopkins Twp. | |
| 1. Public Land Survey | T <u>3N</u> R <u>12W</u> | <u>L-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBR0006 PAGE 54

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert J Jonker, in a field survey on 10-29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set in G.L.O. survey Old Ratekin Notes, no date
1" iron Note: Ratekins sketch
C/L drain SE 5.0' Shows it on straight line
14" Ash NW 25.5' for the mile & at the midpoint
Fe. Cor. post NE. 34.2'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov. 10, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" solid pin 1' below grade
Set 36" std. Allegan Co. Monument
Corner is @ Midpoint of mile, on line between SW. & SE. Corners

Check OK to the ash tree & the drain per part "A" above
 This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Std. Allegan Co. Monument
Found nail-E. NE. side 30" Ash-N30°W 26.12'
A/C remon tag-SW. side 14" Maple N60°W 64.35'
A/C tag & pk. nail-SE. side p. pole S85°W 164.35'
Set cut mark on top of N. side 40" Conc. culv. S03°W 119.89'
A/C remon tag & pk. nail-SW. side p.pole S75°E 191.60'
L-13, Dorr Twp. East 16.58'

Signed by Robert J. Jonker
 Surveyor's Michigan License No. 21572

Date 11-9-98