

RE

MAR 17 2001

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY
Joyce A. Bickel

00 FEB - 1 AM 8:48

LIBER 007 PAGE 93
FILED

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 3N R. 13W	A-11
SW COR. SEC. 30	T. R.
NW COR. SEC. 31	T. R.
T. 3N., R. 13W.	T. R.
MONTEREY TWP.	T. R.
2. Property Controlling in section	S. T. R.
	S. T. R.
3. Miscellaneous Property in Sec.	S. T. R.
4. Lot No., Recorded Plat.		
5. Private Claims.		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

* SEE BACK OF SHEET FOR CORNER HISTORY *

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999.
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON BAR PER ITEMS 7-14 LISTED IN PART A ABOVE.
CORNER AS FOUND IS ON RANGE LINE.
SET STANDARD ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.
ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON DEC. 14, 1999.
TOTAL ON ROAD TRAVERSING = 2641.62'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP
-NAIL IN NE SIDE 60" OAK N51W 33.45'
-NAIL IN N. SIDE SUPPORT POLE N58E 44.32'
-NAIL IN S FACE COR FENCE POST N72W 46.76'
-FACE ST. SIGN POST S30W 83.45'
-M-11, T3N, R14W SOUTH 42.14'

Raymond Moored Date 12/24/99

Surveyors License No. 26463



MAR 07 2000

ALLEGAN COUNTY
MONTEREY TOWNSHIP
T.3N., R.13W.

SECTION

A-11

LIBER 007 PAGE 94

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O. WEST BETWEEN SEC'S 30 & 31
77.67 TO W. BNDRY 69 LKS N. OF POST AND SET COR TO SEC. 30 & 31
A BEECH 11 in. BEARS N21E 16 LKS
A BEECH 20 in. BEARS S61E 60 LKS

2. COUNTY SURVEYOR NOTES, BLACK BOOK
STONE

3. MITCHELL SURVEYS, INC., ACT 132 SURVEY, 4-19-79
IRON BAR
-POW POLE SE 63.56
-50" OAK WNW 33.50
-TELE POLE NW 44.23
-HEATH COR SOUTH 41.83
-A-11 EAST TO B-11 = 2491.85'
-A-11 SOUTH TO A-12 = S01°-48'-40"W 2669.18'

4. DONALD RATEKIN SECTION CARD INFORMATION
SW COR. FD. SLEIGH SHOE 5-1980
-HEATH COR S. 41.78 (1/2" IRON IN CONC.)
-NAIL IN SE SIDE GUY POLE N55°E 44.38
-NAIL IN NE SIDE P. POLE S45°E 63.52
-NAIL IN SW SIDE 40" OAK N60°W 33.45'

5. JOHN H. DILLINGHAM, BOUNDARY SURVEY, 6-6-80
A-11 EAST TO B-11 = 2491.73

6. TRI-COUNTY LAND SURVEYS, BOUNDARY SURVEY 3-19-84
FOUND IRON

7. DAVID F. PEABODY, L.C.R.C. REC. LIBER 4 PAGE 27, 1-23-92
FOUND 1" X 1 1/2" IRON
-42" OAK N85°W 31.5'
-P. POLE S40°E 63.5' TO NAIL
-NW COR. HOUSE S45°E 100.0'
-3/8" IRON SOUTH 41.8'

8. WIGHTMAN MOORED INC., BOUNDARY SURVEY, 10-03-82
A-11 EAST TO B-11 = 2491.73

9. KIRK L. VANORDER, ACT 132 SURVEY, 12-4-82, NW 1/4 SEC 31
FD. 1" X 2" STEEL BAR
-FEN. COR. POST W.NW 46.75'
-SUPPORT POLE NE 44.42'
-POWER POLE SE 63.56'
-ST. SIGN SW 83.60'
-CONC. MON S. 41.815 (HEATH COR.)

10. KIRK L. VAN ORDER, ACT 132 SURVEY IN THE SW 1/4 SEC 30, 7-13-84
FD 1-1/3" X 1" STEEL RAIL
-SET NAIL IN NE SIDE 43" W. OAK NW 33.41'
-NAIL IN S. SIDE WOOD COR. FEN. POST W., NW 46.71'
-SET NAIL IN NW SIDE SUP. POLE NE 44.27'
-SET NAIL IN NE SIDE P. POLE SE 63.62'
-A-11 NORTH TO A-10 = 2619.48'

11. KIRK L. VAN ORDER, ACT 132 SURVEY IN SW 1/4 OF SEC. 30, 11-7-95
SHOWS SAME WITNESSES AS #9 ABOVE
-A-11 EAST TO B-11 = 2491.52

12. WIGHTMAN MOORED, INC., FIELD NOTES DATED: 2-14-96
A-11 NORTH TO A-10 = 2619.48 (KVO)
2619.61 (DAR)
A-11 EAST TO B-11 = 2491.52 (KVO)
2491.73 (DAR)

13. KIRK L. VAN ORDER, ACT 132 SURVEY IN NW 1/4 OF SEC. 31, 4-13-98
SHOWS SAME WITNESSES AS #9 ABOVE
A-11 EAST TO B-11 = 2488.785' N88°-22'-14" E

14. HOLLAND ENGINEERING SECTION CARD
SHOWS SAME WITNESSES AS DAVID F. PEABODY DOES IN #6

15. DESCRIPTION OF HEATH & MONTEREY DRAIN
QUOTE "COMMENCING 42.44 RODS S OF THE NW COR. OF SAID SEC 31"

