

MAR 16 1994

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
(County)

Located In:

Corner Code ~~##~~

- 1. Public Land Survey T 3N R 13W B-1(N 1/4, 6)
 T R Monterey Twp.
 T R _____
 T R _____
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
James W. Chittick

1993 DEC 17 PM 1:55

FILED

I, John C. Bueche, in a field survey on October 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|----|----|----|----|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | 9 | 8 | 7 | 6 | 5 | 4 | 3 | 2 | 1 | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 13 | 12 | 11 | 10 | 9 | 8 | 7 | 6 | 5 | 4 | 3 | 2 | 1 |
| 9 | | | | | | | | | | | | | |
| 10 | 16 | 15 | 14 | 13 | 12 | 11 | 10 | 9 | 8 | 7 | 6 | 5 | 4 |
| 11 | | | | | | | | | | | | | |
| 12 | 19 | 18 | 17 | 16 | 15 | 14 | 13 | 12 | 11 | 10 | 9 | 8 | 7 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

B-1 Not set by GLO
 Iron 1968
 18" Hickory NE 32.2' 2439.04' W to NW 6
 TP NE 48.6' 2445.24' E to NE 6
 18" Hickory NE 50.4' 33' E to S 1/4 31, 4-13
 12" Elm 43.9' (no direction)
 20" Hickory NW 120.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


B-1 Found 2" x 18" sq. shaft down 1'
 18" Hickory NE 50.4'
 Cor. is on line between the SW & S 1/4 Sec. 31, 4-13 & 33' W
 of S 1/4
 Meas. W to NE 6, 2439.74'
 Meas. E to S 1/4 31, 4-13, 33.00' on line between S 1/4 & SW 31, 4-13

This position not established by original government surveyors.
This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Replaced 2" shaft with Std. Allegan Co. Mon. (3/4" x 24" rod & cap)
 Allegan Co. Remon. Tag & Conc. Nail in N side TP S 75° W 211.91' EDM
 Allegan Co. Remon. Tag & Conc. Nail in E side 10" Maple S 05° E 51.86' EDM
 Allegan Co. Remon. Tag & Conc. Nail in W side 20" Hickory N 43° E 50.66'
 Allegan Co. Remon. Tag & Conc. Nail in W side 12" Elm S 65° E 76.33'
 Allegan Co. Mon. & Cap E 33.00' (S 1/4, 4-13)
 On tree line to N
 C/L E-W gravel road is N 2'±
 C/L two track N is E 18'±
 Meas. by hand

Signed by John C. Bueche Date Oct 26, 1993
 Surveyor's Michigan License No. 13027



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983