

MAR 16 1994

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
(County)

Located In:	Corner Code #
T <u>3N</u> R <u>13W</u>	<u>C-1(NE, 6)</u>
T _____ R _____	<u>Monterey Twp.</u>
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1993 DEC 17 PM 1:55
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	3	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on October 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1 1 1/2" pipe, LCRC L2, P92
 5-5-73 2645.24' W to N 1/4 6
 SW 44.62' TP 2632.24' E to N 1/4 5
 SE 34.71' st. sign 33' E to SE 31, 4-13
 NE 78.35' TP
 N 80.85' Tw. Cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


C-1 Found capped iron down 7" 32.6' W of SE 31 & 0.3' N of line between S 1/4 31 & SE 31
 Set point 33.00' W of SE of 31 & on line between S 1/4 & SE 31
 SW 44.62' TP
 Meas. W to N 1/4 6, 2645.06'
 Meas. E to SE 31, 4-13, 33.00' on line between S 1/4 & SE 31, 4-13

And is accepted as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Set Std. Allegan Co. Mon. (3/4" x 24" Pin no cap)
 Conc. Nail & Allegan Co. Remon. Tag in N side 16" Cedar S 60° E 87.75'
 Conc. Nail & Allegan Co. Remon. Tag in E side 18" Ch. Elm S 15° E 78.90'
 Conc. Nail & Allegan Co. Remon. Tag in E side TP S 45° W 44.04'
 Conc. Nail & Allegan Co. Remon. Tag in S side 6" x 8" fence cor.
 N 65° E 70.68'
 C/L gravel road E-W, N 3'±
 C/L gravel road N, E 25'±
 C/L gravel road S, E 4'±
 Iron 0.30' N & 0.40' W
 Meas. by hand

Signed by John C. Bueche Date Oct 26, 1993
 Surveyor's Michigan License No. 13027



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983