

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

LIBRO 006 PAGES 10

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T... <u>3N</u> R... <u>13W</u>	<u>C-5</u>
SEC. COR COMMON TO SEC. 7, 8, 17 & 18 MONTEREY TWP.	T..... R.....
	T..... R.....
	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No.....Recorded Plat.....		
5. Private Claims.....		

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		9		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Aug. 5, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO
80 SET POST COR SEC 7, 8, 17 & 18
A W. OAK 20 IN DIA BEARS S.3°E. 20 LKS DIST
A MAPLE 15 IN DIA BEARS N.31°W 10 LKS DIST

SURVEY BY MOORED LAND SURVEYS, DATED 10-08-96
FOUND 2 1/2" PIPE FOR CORNER.
-12' NORTH OF TRAIL TO WEST
-C/L N&S ROAD EAST 10'+/-
-FD. NAIL & TAG IN NW SIDE 20" WILLOW NE 51.67'
-FD. NAIL & TAG IN S SIDE 10" MAPLE WNW 39.95'
-FD. NAIL & TAG IN SE SIDE 10" PINE SW 47.08'
-MEAS EAST TO D-5 2660.58'
-MEAS SOUTH TO C-6 2662.78'

KIRK VAN ORDER, SURVEY DONE 1997
FD. 2 1/2" PIPE FOR CORNER
-FD. NAIL & EXXEL TAG IN NW SIDE 21" WILLOW NE 51.69'
-FD. NAIL & EXXEL TAG IN S SIDE 8" MAPLE WNW 39.98'
-FD. NAIL & EXXEL TAG IN SE SIDE 10" PINE SW 47.12'
-C/L N & S ROAD EAST 9' +/-
-C/L TWO-TRACK ROAD TO WEST SOUTH 10'+/-

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED SEPT. 8, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2 1/2" PIPE PER MOORED AND VAN ORDER INFORMATION LISTED ABOVE.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SET STANDARD 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON W/ CAP INSIDE 2 1/2" PIPE.

PEER GROUP APPROVED ON SEPT. 8, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
-FD. NAIL & EXXEL TAG IN NW SIDE 20" WILLOW N50E 51.67'
-FD. NAIL & EXXEL TAG IN S SIDE 10" MAPLE S70W 39.95'
-FD. NAIL & EXXEL TAG IN SE SIDE 10" PINE S35W 47.08'
-C/L TWO TRACK ROAD TO WEST SOUTH 12' +/-
-C/L NORTH-SOUTH ROAD EAST 10' +/-
-DIST EAST TO D-5 2660.58'
-DIST SOUTH TO C-6 2662.78'

Raymond Moored Date 9/18/98

Surveyors License No. 26463

