

**Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MAR 16 1994

For corners in

Allegan County

COMMITTEE (County)

Located In: Monterey Twp. Corner Code #/

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T _____ R _____          | _____      |
|                                    | T <u>3N</u> R <u>13W</u> | <u>C-7</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

1993 DEC 30 PM 2:43

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	10						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on December 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

\*recorded in LCRC on

A. Description of original monument and accessories and/or subsequent restoration:

Medema, VanKooten & Assoc.	Wightman Moored, Inc. 2-27-93, 3/4" Iron
1" iron, 1980,*L. 003, P. 322	24" Oak N 45° W 49.84'
PK W. side P. pole SW 54.74'	40" Oak N 15° E 134.25'
Nail SW side 24" Hick. NW 49.86'	18" Maple S 45° E 80.36'
Nail NW side 20" Hick. SW 70.48'	P. pole N 20° W 132.44'

Original GLO survey - post	Mitchell Surveys, 1988, 1" Bar
24" Pine N 71° W 10 links	TCB SE 41.27'
19" Pine N 58° E 15 links	P. pole SW 54.35'
	24" Hick. NW 49.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4"x12" star drill set on end by wit. of Wightman Moored, 1993.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4"x36" standard capped Allegan Co. Mon.  
 Found spk NE side 24" Oak N 45° W 49.84'  
 Found spk E. side P. pole N 20° W 132.44'  
 Found spk W. side 40" Oak N 15° E 134.25'  
 Found spk SW side 18" Oak S 45° E 80.36'  
 Found spk E. side P. pole S 28° W 54.41'  
 on C/L "X" of roads and is accepted as the best available evidence of the position of the original corner.

Signed by Robert J. Jonker Date 12-13-93  
JONKER LAND SURVEYS  
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

Part "A" continued

LIBER 004 PAGE 315

Holland Engineering, 1978

24" Maple NW 49.87'

24" Maple SW 70.5'

St. sign NE 54.75'