

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Allegan (County) Located In: Corner Code #

1. Public Land Survey T 3N R 13W C-13 SW Cor
 T ___ R ___ Sec 32
 T ___ R ___ Monterey Twp.
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 1994 DEC 30 PM 12:16
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on December 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13 Gen. Land Office Survey Notes 1831 Lucius Lyon, Surveyor Set Post 7" Beech N80°E 26 links 9" Beech N35°W 15 links	C-13 No old County Surveyor witness ties exist for this corner
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13
 Found 1" iron and accepted it as a careful and faithful perpetuation of the position of the original corner.
 Found Nail & Tag in NE Side Corner Railroad Tie AZ. 270° 0.73'
 Found Nail in E Side 16" Cherry AZ. 171° 34.49'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY

DATE APPROVED 12-13-94
 COUNTY REP. John P. Clapp

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Set A.C. Remon Iron and Cap		
A.C. Remon Tag & Nail in NE Side 10" Cherry	AZ. 330°	31.28'
A.C. Remon Tag & Nail in NW Side 6" Cherry	AZ. 71°	23.41'
A.C. Remon Tag & Nail in E Side 16" Cherry	AZ. 171°	34.37'
A.C. Remon Tag & Nail in N Side 8" Poplar	AZ. 263°	35.88'
C-1, T2N, R13W	AZ. 90°	13.86'

Signed by John P. Clapp Date Dec. 13, 1994

Surveyor's Michigan License No. 1409

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
 NO REVISIONS UNTIL 1975
 1409 REVISED 1983

