

MAR 10 1994

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
COMMISSION
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 3N R 13W D-1(N 1/4, 5)
T ___ R ___ Monterey Twp.
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

1993 DEC 17 PM 1:55

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, John C. Bueche, in a field survey on October 26, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-1 Not set by GLO
- 5/8" rod, LCRC L2, P92, 5-8-73 2632.24' W to NW 5
- On line 1/2 way between sec. cor. 2632.24' E to NE 5
- SW 56.61' 15" Ash 49.88' E to S 1/4 32, 4-13
- SE 54.31' Ash (no size)
- NE 34.40' clump trees

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-1 Found 1/2" rered down 4", 49.95' W of S 1/4 32 and on line between S 1/4 & SE 32, 4-13
- On field division S (E edge woods)
- NE 34.40' clump trees
- Meas. W to NW cor. 5, 2632.45'
- Meas. E to S 1/4 32, 4-13, 49.95' on line between S 1/4 & SW 32, 4-13

This position not established by original government surveyors.
This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 Replaced rered with Std. Allegan Co. Mon. (3/4" x 24" Pin & Cap)
- Conc. Nail & Allegan Co. Remon. Tag in E side 10" Hickory N 35° E 52.70'
- Conc. Nail & Allegan Co. Remon. Tag in SE side 10" Oak N 70° E 75.47'
- Conc. Nail & Allegan Co. Remon. Tag in E side 16" Oak S 30° W 57.43' (4.5' high)
- Conc. Nail & Allegan Co. Remon. Tag in E side 20" Oak S 25° E 54.95'
- On E edge wood S
- C/L two track S, E 13'±
- On C/L gravel road, E-W
- Meas. by hand

Signed by John C. Bueche Date oct 24 1993
Surveyor's Michigan License No. 13027

