

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

LIBERO 006 PAGES 11

FOR CORNERS IN: ALLEGAN COUNTY

1. Public Land Survey LOCATED IN: T. 3N R. 13W CORNER CODE # D-5

1/4 SEC. COR COMMON TO SEC. 8 & 17 MONTEREY TWP.

2. Property Controlling in section S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	-	-5	-	4	-	-3	-	2	-	-1	-	-
3													
4	7	-	8	-	9	-	10	-	11	-	12	-	-
5													
6	18	-	17	-	16	-	15	-	14	-	13	-	-
7													
8	19	-	20	-	21	-	22	-	23	-	24	-	-
9													
10	30	-	29	-	28	-	27	-	26	-	25	-	-
11													
12	31	-	32	-	33	-	34	-	35	-	36	-	-
13													

I, Raymond Moored in a field survey on Aug. 5, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO
40.25 SET OR SEC POST
-A W. OAK 28 IN DIA BEARS S26W 29LKS DIST
-A PINE 30 IN DIA BEARS N72E 11 LKS DIST

JONKER, 1990 SURVEY
-S 1/4 POST OF SEC. 8, FD REROD, NO WITS
-N 1/4 POST OF SEC. 17, NO INFO

NO OTHER CORNER HISTORY AVAILABLE

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED SEPT. 8, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD PER JONKER INFORMATION ABOVE.
FOUND CORNER WAS ON OCCUPATION LINE TO NORTH
MEAS WEST TO C-5 AZ. 270°-14'-44" 2660.58'
MEAS EAST TO E-5 AZ. 89°-15'-32" 2656.72'

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SET STANDARD 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND REROD.

PEER GROUP APPROVED SEPT. 8, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
-NAIL & TAG IN WEST SIDE 36" OAK N25E 23.20'
-NAIL & TAG IN WEST SIDE 10" OAK NORTH 40.15'
-NAIL & TAG IN SOUTH SIDE 20" WALNUT N75W 79.54'
-NAIL & TAG IN WEST SIDE 6" OAK S25W 53.63'
-MEAS WEST TO C-5 AZ. 270°-14'-44" 2660.58'
-MEAS EAST TO E-5 AZ. 89°-15'-32" 2656.72'
-ON OCCUPATION LINE TO NORTH

Raymond Moored Date 9/18/98

Surveyors License No. 26463

