

**Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**MAR 16 1994**  
For corners in

**Allegan County**  
COMM. COUNTY

Located in: Monterey Twp. Corner Code ##

|                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>3N</u> R <u>13W</u> | <u>D-7</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |

*Robert J. Jonker*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN

1993 DEC 30 PM 2:43

**FILED**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 10 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Robert Jonker, in a field survey on December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

|   |  |
|---|--|
| 1869, Hicks, Stone                          | 1993, Wightman & Moored Inc. Stone with drill hole |
| 20" Oak SW 46.2'                            | 33" Walnut S 5° E 42.01'                           |
| B. Walnut 3' S 42.5'                        | 12" Maple S 45° W 122.67'                          |
| 1988, Mitchell Surveys, Stone 10' S. of C/L | 48" Cherry N 10° W 70.06'                          |
| 1991, Kirk VanOrder, Stone                  | NE cor metal bldg. S 30° W 95.83'                  |
|   | NE cor hse (porch) S 75° W 115.92'                 |
|   | Original GLO notes - set post                      |
|   | B. Oak 14", S 20° E 24 links                       |
|   | B. Oak 14", N 40° W 29 links                       |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone 8" below grade, with drill hole by 1993 wit. listed in "A" above, top stone was over a 2nd and a 3rd stone to a depth of 36".



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced all 3 stones, with a 3/4"x36" standard capped Allegan Co. Mon.  
 Found spk W. side 33" Walnut S 05° E 42.01'  
 Found spk E. side 12" Walnut S 45° W 122.67'  
 Found spk E. side 48" Cherry N 10° W 70.06'  
 Found spk E. side 18" Walnut N 35° E 40.34'  
 NE cor hse (porch) S 75° W 115.92'  
 C/L road North 10'±

This location is accepted as the best available evidence of the position of the original corner.

Signed by Robert J. Jonker  
JONKER LAND SURVEYS  
 Surveyor's Michigan License No. 21572

Date 12-13-93

LIBER **004** PAGE **316**

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971  
 REVISED MAY 11, 1975  
 REVISED JAN., 1983

Over for Sheet 2

Part "A" continued

1869, Hicks, Stone

|              |    |       |
|--------------|----|-------|
| 20" Oak      | SW | 46.2' |
| 3" B. Walnut | S  | 42.5' |

Holland Engineering - no date

|                                 |     |        |
|---------------------------------|-----|--------|
| R.R. spike Midway (not on line) |     |        |
| 20" Ash                         | NE  | 37.74' |
| 40" Oak                         | WSW | 45.02' |
| 24" Ash                         | SSE | 49.00' |
| Angle iron fce post             | SE  | 27.50' |

1991 survey by Kirk VanOrder Found Iron

Found Stone

|                    |     |        |
|--------------------|-----|--------|
| 50" Oak            | WSW | 47.33' |
| 33" Walnut         | SSE | 42.05' |
| NW cor metal bldg. | SW  | 95.97' |
| Spike              | ESE | 38.83' |
| 25" Walnut         | NE  | 40.24' |

1988, Mitchell Surveys

Stone 10' S. of C/L

|                    |     |         |
|--------------------|-----|---------|
| 20" Walnut         | SSW | 42.0'   |
| 36" Oak            | SW  | 47.3'   |
| 14" Walnut         | NNW | 55.9'   |
| 24" Walnut         | NE  | 45.7'   |
| NE cor metal bldg. | SSW | 95.95'? |